

**CITY OF HOUSTON  
DEPARTMENT OF PUBLIC WORKS  
AND ENGINEERING**

**ENGINEERING DESIGN MANUAL  
FOR  
SUBMERSIBLE LIFT STATIONS**



**Dale A. Rudick, P.E.  
Director**

**J. Timothy Lincoln, P.E.  
City Engineer**

**July 2016**

## **TABLE OF CONTENTS**

SECTION 1:	INTRODUCTION .....	1
1.01	Purpose .....	1
1.02	General.....	1
D.	Influent Flows .....	1
1.03	Standards and Codes.....	2
1.04	Definitions .....	2
SECTION 2:	LIFT STATION CONFIGURATION .....	6
2.01	Lift Station New Construction and Replacement Design.....	6
SECTION 3:	SITE REQUIREMENTS .....	8
3.01	Lift Station Site Selection and Use.....	8
3.02	Access.....	9
3.03	Security .....	10
3.04	Landscaping.....	11
3.05	Flood Plain/Floodway.....	11
3.06	Site Drainage .....	11
3.07	Odor Control.....	11
3.08	Corrosion Control .....	14
SECTION 4:	LIFT STATION HYDRAULIC DESIGN.....	15
4.01	System Head and Pump Capacity Curves .....	15
4.02	Wet Well Design .....	16
4.03	Wet Well Levels .....	17
4.04	Lift Station Bypass .....	17
SECTION 5:	MECHANICAL DESIGN .....	18
5.01	General.....	18
5.02	Pump Selection .....	18
5.03	Valves .....	19
5.04	Plumbing.....	20
5.05	Air Conditioning (A/C) .....	21
5.06	Ventilation .....	22
SECTION 6:	STRUCTURAL DESIGN.....	24
6.01	General.....	24

6.02	Design Standards .....	24
6.03	Geotechnical Coordination .....	25
6.04	Loads .....	25
6.05	Buoyancy .....	26
6.06	Design Stresses .....	26
6.07	Design Considerations .....	27
6.08	Detailing .....	29
6.09	Handrails .....	29
<b>SECTION 7: ELECTRICAL DESIGN .....</b>		<b>31</b>
7.01	Design Standards .....	31
7.02	Basis of Design .....	31
7.03	Electrical Drawing Set .....	32
7.04	Indoor Electrical Symbols, Legend, Lighting Fixture Schedule & Abbreviations Sheet 34	
7.05	Site Plan .....	34
7.06	Electrical Plans and Sections .....	34
7.07	Typical Details .....	35
7.08	Control Building Plan .....	35
7.09	Control Cabinet Layout .....	36
7.10	Process and Instrumentation Diagrams .....	36
7.11	Control System Wiring Diagrams .....	36
7.12	Wireless Communication and Site Monitoring Equipment .....	36
7.13	MCC & Power Wiring Diagram .....	36
7.14	Single Line Diagrams .....	36
7.15	Conduit Schedule .....	36
7.16	Device Ratings Schedule .....	37
7.17	MCC Elevations (Drawing View) .....	37
<b>SECTION 8: FORCE MAIN DESIGN .....</b>		<b>38</b>
8.01	Sizing Limitations .....	38
8.02	Flow Velocity .....	38
8.03	Detention Time .....	38
8.04	Alignment Criteria .....	38
8.05	Discharge Manhole .....	38
8.06	Pipe Material .....	39

8.07	Water Hammer and Surge Analysis .....	39
8.08	Force Main Pipe Valves and Drains .....	39
8.09	Downstream Hydraulic Capacity.....	39

APPENDIX A – Design Guideline Drawing Sheet List

APPENDIX B – List of Design Requirements and Considerations

APPENDIX C – Sample Calculations

APPENDIX D – Basis of Design Report Requirements for ETJ

APPENDIX E – Sample Drawing Markup

**List of Tables**

Table 1. Submersible Lift Station Sizing.....	7
Table 2. Biofilter Design Values .....	13
Table 3. Chemical Feed System Design Values .....	14
Table 4. Design Values for Cycle Time.....	16

**SECTION 1: INTRODUCTION**

**1.01 Purpose**

- A. The Design Guidelines Manual for Submersible Lift Stations provides requirements, criteria, and considerations for the consistent and uniform design of lift stations and force mains for the City of Houston (COH). These guidelines apply to the design of new COH Capital Improvement Plan (CIP) lift station and force main projects constructed within the COH city limits, and lift stations and force mains constructed within the COH Extraterritorial Jurisdiction (ETJ). The guidelines represent COH minimum design requirements and are to be used with the Design Guideline Drawings for Submersible Lift Stations. The Design Guideline Drawings sheet index is included as Appendix A. The Design Engineer is responsible for use of these guidelines and application to specific project conditions and requirements.

**1.02 General**

- A. The Design Engineer is responsible as the Engineer of Record (EOR) for a complete and coordinated set of drawings. The Design Guideline Drawings for Submersible Lift Stations must be customized by the EOR to be project-specific. The drawings cannot be used without additional engineering and drafting by the EOR and without supplemental drawings prepared by the EOR.
- B. COH lift station and force main CIP projects shall be planned and designed utilizing planning data, empirical flow data, and information provided by the COH Infrastructure Planning Branch (IPB). COH CIP projects shall be designed per specific contract requirements. Appendix B is included as a list of design requirements and considerations for use by the Design Engineer, in addition to the requirements of this Design Guidelines Manual. Lift stations and force mains shall comply with the requirements of the latest Texas Commission on Environmental Quality (TCEQ) 30 TAC Chapter 217, Design Criteria for Wastewater Systems.
- C. For private development in the COH ETJ, a basis of design report shall be submitted for all lift station and force main projects and shall address the design requirements listed in Appendix C.
- D. Influent Flows
  - 1. Determination of design flows for the current and future conditions shall be coordinated with the IPB through COH project manager for all CIP projects.
  - 2. For other lift station projects, flow determination shall be described in the basis of design report.

1.03 Standards and Codes

- A. Lift station and force main designs shall be in compliance with the latest editions of the COH Infrastructure Design Manual, Standard Details, and Standard Specifications.
- B. Design of lift stations, force mains, and ancillary facilities shall conform to all applicable local, state, and federal regulations and national standards including but not limited to those of:
  - 1. American Association of State Highway and Transportation Officials (AASHTO)
  - 2. American Concrete Institute (ACI)
  - 3. American Institute for Steel Construction (AISC)
  - 4. American National Standards Institute (ANSI)
  - 5. American Society of Mechanical Engineers (ASME)
  - 6. American Society for Testing and Materials (ASTM)
  - 7. American Water Works Association (AWWA)
  - 8. City of Houston Code of Ordinances
  - 9. Environmental Protection Agency (EPA)
  - 10. Hydraulic Institute (HI)
  - 11. Institute of Electrical and Electronics Engineers (IEEE)
  - 12. National Electrical Code (NEC)
  - 13. National Electrical Manufacturers Association (NEMA)
  - 14. National Fire Protection Association (NFPA)
  - 15. Occupational Safety and Health Act (OSHA)
  - 16. Texas Commission on Environmental Quality (TCEQ)

1.04 Definitions

- A. The following terms used in this guideline are defined as below unless the context clearly states otherwise.
  - 1. Alternate High Lift Station Configuration – Lift station configuration with discharge piping and valves located above grade.

2. Alternate Low Lift Station Configuration – Lift station configuration with discharge piping and valves located in a below grade, enclosed valve vault.
3. Backflow Preventer – A device installed in potable water piping to prevent the flow of nonpotable water into a potable system.
4. Best Efficiency Point – The discharge rate at which an impeller of a given diameter rotating at a given speed operates at maximum efficiency.
5. Bypass – The intentional diversion of a waste stream.
6. Collection System – Pipes, conduits, lift stations, force mains, and all other constructions, devices, and appurtenant appliances used to transport domestic wastewater to a wastewater treatment facility.
7. Control Building/ Room – The superstructure of a pumping station, which usually includes electrical equipment and may also include motors.
8. Design Engineer – Engineer of Record and/or engineering firm selected for the project design.
9. Design Life – The length of time that an engineering structure or device is intended to function without failing.
10. Discharge Head – Static head plus friction headloss (in discharge piping) plus velocity headloss at the end of the discharge piping.
11. Fillet – Concrete in the bottom of the wet well shaped to smooth liquid flow into the pump suction openings and to prevent the accumulation of solids.
12. Firm Capacity – The maximum flow rate achievable, under design conditions, with the largest pumping unit out of service.
13. Flooded Suction – Condition in which the pump volute is below the low water level of the wet well.
14. Force Main – Piping, external to the lift station and filled with liquid under pressure, through which the station discharges.
15. High Water Level – Water surface elevation corresponding with “All Pumps On” level and shall be no higher than the elevation required to prevent sanitary sewer overflows in the upstream collection system. Note: This elevation will be provided for COH CIP projects by the IPB.
16. Influent – Liquid that flows into a process or confined space. This term may also be used to identify items or properties associated with influent.



17. Intake – A structure from which the pumps take suction.
18. Invert – The inside bottom of a pipe.
19. Lift Station – A structure that collects wastewater and uses pumps to raise it to a higher elevation. The term lift station applies to a structure in which the static head exceeds the frictional head losses.
20. Low Water Level – Water surface elevation corresponding with “All Pumps Off” level.
21. Net Positive Suction Head (NPSH) – Absolute dynamic head of the pumped liquid at the suction eye of a pump.
22. Net Positive Suction Head Available (NPSH<sub>A</sub>) – The NPSH at which the pump in a given system operates at a given discharge rate.
23. Net Positive Suction Head Required (NPSH<sub>R</sub>) – The minimum NPSH at which a pump can properly operate for a given discharge rate.
24. Operating Point – The head and discharge at which a pump operates in a system. It is the intersection of the pump curve and the system curve.
25. Preferred Lift Station Configuration – Lift station configuration with discharge piping and valves located in a below grade, grated valve vault.
26. Runout – Region on pump curve the pump discharge head decreases rapidly. It is occurs typically near the maximum discharge flow.
27. Shut-off Head – The head developed by a pump at zero discharge rate (against a closed discharge valve).
28. Static Head – The difference in elevation between the surface of the pool from which the pump draws water and the surface of the pool into which the outlet discharges.
29. Submersible Pump – A pump or pump and motor suitable for fully submerged operation.
30. System Head Curve – Curve of total dynamic head versus flow for all flow rates within the capability of the pumping station.
31. Total Dynamic Head (TDH) – The total head at which a pump operates at any given discharge rate.
32. Water Hammer – Surge pressure or water hammer in a force main is created by any change from a steady state flow condition, and may range from only slight pressure and/or velocity changes to sufficiently high vacuum or pressure conditions which may

cause the collapse or rupture of the pipeline, or cause damage to pumps and/or valves. Water hammer is typically caused by the opening, closing or regulating of valves, by the normal operation of starting and/or stopping of pumps, pump power failure, or a major pipeline rupture.

33. Wet well – A pumping station or a portion of a pumping station that stores the wastewater being pumped.

## **SECTION 2: LIFT STATION CONFIGURATION**

### **2.01 Lift Station New Construction and Replacement Design**

- A. The Design Engineer shall use the latest COH Design Guideline Drawings for Submersible Lift Stations. The Design Engineer must receive approval from the Director or the designated representative for any alternative designs or deviations.
- B. Designs shall be completed in accordance with these guidelines and applicable regulatory requirements, best practices, and national standards.
- C. General Lift Station Configuration Guidance
  - 1. Design Engineer shall provide recommendations and justification for selected lift station configuration (See Definitions for Preferred, Alternate High, or Alternate Low).
  - 2. Using the latest COH Design Guideline Drawings, remove all notes to Design Engineer (shown in *Italics*) and provide all information shown as *TBD* or as otherwise instructed in notes to Design Engineer. Revise sheet numbers, title block information, etc. as appropriate for specific project contract drawing package.
  - 3. Dimensions on the COH Design Guideline Drawings which are modified by "max" or "min", but which need to be selected as a definite dimension by the Design Engineer shall have the appropriate dimension included without the modifier.
  - 4. Design Engineer shall edit and supplement the COH Standard Specifications as needed for the specific project. Delete or indicate as "Not Applicable to this Project" where materials or equipment included in the specifications is not used for the specific project.
  - 5. Design documents must be sealed and signed by a Texas Licensed Professional Engineer.
  - 6. Table 1 includes sizing guidelines for submersible lift station facilities.

**Table 1. Submersible Lift Station Sizing**

LS Series	Number of Pumps	Individual Pump Capacity – GPM		Lift Station Firm Design Capacity – GPM		Pump Discharge Piping -Inches		Minimum Wet Well Diameter - Feet	Minimum Site Size
		From	To	From	To	From	To		
A	2	-	199	-	199	4	4	6	55'x55'
B	2	200	499	200	499	4	8	8	55'x55'
C	2	500	999	500	999	8	10	10	70'x70'
D	3	250	500	500	1,000	6	10	10	70'x70'
E	3	500	999	1,000	1,998	8	10	12	75'x75'
F	3	1,000	1,399	2,000	2,798	10	12	14	75'x75'
G	3	1,400	1,999	2,800	3,998	12	16	16	75'x75'
H	3	2,000	3,499	4,000	6,998	16	24	21	85'x85'
I	4	500	2,500	1,500	7,500	10	24	21	85'x85'
J	4	800	3,499	2,400	10,497	15	30	24	85'x85'
K	5	2,500	3,999	10,000	15,996	18	20	30	95'x95'
L	2-DWF	-	999	-	999	4	10	25	90'x90'
	4-WWF	250	3,499	750	10,497	16	24		
M	6	3,000	5,299	15,000	26,495	18	20	40	110'x110'
N	2-DWF	100	2,000	100	2,000	4	10	28	95'x95'
	4-WWF	3,500	5,300	10,500	15,900	16	24		

Note: <sup>(1)</sup> The physical dimensions of the wet well and valve vaults in Table 1 were sized to accommodate the maximum pipe and valve sizes required to pump the maximum range of pumping capacities per pump for each series of lift stations.

- Design Engineer shall determine the depth of wet well, elevation of pump suctions, and elevation of inflow pipe.

### **SECTION 3: SITE REQUIREMENTS**

#### **3.01 Lift Station Site Selection and Use**

- A. The evaluation for selection and use of lift station sites shall address the following:
1. Visual impact on the neighborhood. Sufficient setback from the property line to the fence line should be provided to accommodate the required landscape buffer. In all cases, setback from property lines as governed by COH ordinances should be followed.
  2. Access to areas of the site to allow for staging and positioning of vehicles and equipment used to remove pumping equipment from wet well, including adequate access roadway widths and turning radii. Site pavement areas shall be sufficient to accommodate lifting and maintenance equipment.
  3. Fencing location. Generally, the entire site within the fenced area is paved. Locate the fence one foot inside the paved area. Where adjacent to existing structures, locate the fence further in the site to provide a minimum 6-foot clearance for grounds maintenance.
  4. For facilities that require chemical feed and storage equipment, site access road geometry shall be designed to accommodate movement of largest vehicle required for operation and maintenance of odor control systems.
  5. Clearance for operation and maintenance activities.
  6. Site safety and security.
  7. Odor potential and impact to the neighborhood. Odor control measures shall be provided for all lift stations on an as needed basis.
  8. Structure depth and its potential impact on adjacent areas, including construction activities such as excavation and driving piling.
  9. Location of site with respect to FEMA floodplain and floodway zones.
- B. Refer to Section 2: “Lift Station Configuration” for minimum site dimensions.
- C. The site of the lift station should generally be located on a full parcel. Lift stations should not be located in :
1. Street rights-of-way
  2. Easements

3. Areas where future maintenance access, security, or odor mitigation could become difficult.
  4. Sites where topography will not allow the top or main floor of the station to meet the COH Code of Ordinances, Chapter 19.
  5. Site cannot be made accessible during a flood event as per latest TCEQ regulations.
- D. At least 20 feet clearance between all sides of the lift station facilities and fence line should be provided where feasible.
- E. To the extent possible, lift stations should be oriented such that sources of potential odor release, such as wet well vents, do not adversely affect adjacent areas or sensitive equipment, such as electrical equipment and building air intakes.
- F. Lift stations located in a residential area should acquire an entire residential lot for the site. Subdividing the lot should be avoided.

### 3.02 Access

- A. Locate site security fence and entrance gate to allow a minimum 25-ft long vehicle to access site without blocking main roadway. Pavement of area from main roadway to entrance gate shall be 24 feet wide.
- B. Design site paving geometry to provide an area that will allow a 25-ft long vehicle to turn around within the fenced site area.
- C. Sites with proposed chemical storage tanks should include the following:
1. Provide roadway turnout of appropriate geometry such that chemical delivery truck does not block the main roadway when making a delivery. Truck turnout inside radius should not be less than 50 feet.
- D. Access roadway width should not be less than 20 feet and turnout radius should not be less than 30 feet inside (50 feet preferred) or such greater dimension as necessary to prevent truck or crane wheel overrun from the pavement.
- E. Crane access and setting location to be used for lifting out submersible pumps or other equipment should be specifically addressed in the facilities layouts.
1. Site size, facilities locations, clearance areas, and orientation of hatches should be coordinated with crane type, dimensions, and capacity necessary to remove and replace the largest pump and motor to be installed at the lift station for ultimate capacity conditions. Lift station shall be located on site such that overhead power lines will not interfere with use of cranes for removal of pumps.

- F. Provide reinforced concrete paving into and within the site meeting H-20 loading requirements.
  - 1. Provide parking spaces only inside the secure site area.
  - 2. Low maintenance paving is defined as reinforced concrete pavement of sufficient design and thickness for loads to be encountered for all operation and maintenance activities. At a minimum, pavement thickness should be 7-inches. For projects in the ETJ areas outside of the COH, an all-weather surface may be acceptable.
  - 3. Turf paver systems should only be used when required by neighborhood for aesthetics.
  - 4. Provide reinforced concrete pavement and/or pervious concrete pavement as required, at uniform elevation, adjacent to and around the lift station. Width should be as necessary for proper mobility of the appropriate vehicle and not less than 20 feet.
  - 5. In order to minimize grounds maintenance and such items as grass and weeds cutting, it is preferred that the reinforced concrete pavement extend one foot beyond the fence line to provide a “mow” strip and minimize maintenance.

### 3.03 Security

- A. The security system should meet all requirements of the latest version of TCEQ Chapter 217, and requirements of the COH Public Works and Engineering Department.
- B. Site security should be provided by a full-perimeter 6-foot high fence topped with 3 strands of barbed wire or an 8-foot high fence. Site access will be through one 16-foot wide, double leaf, inward-opening swing gate secured with a chain and padlock. The fence should also include a pedestrian gate, easily accessed from the entrance drive with the same chain and padlock system described above.
- C. Other intrusion security measures will be considered on a case-by-case basis if special conditions or requirements dictate.
- D. Preferred fence is green PVC-coated, minimum No. 9 gauge galvanized woven wire, 6-foot-high fabric, 2-inch open-diamond mesh pattern, cyclone-type fence with green PVC slats topped with 3 strands of barbed wire.
- E. If determined necessary that fencing materials should match those used in the neighborhood, installing such matching materials on the exterior of the chain link fence for decoration should be considered, as opposed to using an alternative fencing system.
- F. Where necessary to avoid subsidence of fence system based on soil conditions, consider use of a concrete grade beam in which the steel line posts are set. Use minimum 24-inch-deep beam with 6-foot-long concrete support piles spaced not greater than 16 feet on center.

### 3.04 Landscaping

- A. If required, provide landscaping to meet the requirements of the latest COH Code of Ordinances, Chapter 33 “Planning and Development.” As a minimum, provide landscaping that meets the requirements described below.
  - 1. Lift station landscaping design needs to be safe, simple and aesthetically blend into the surrounding landscape. Prefer the use of drought resistant, native plants.
  - 2. All disturbed areas should be grass-sodded with drought-tolerant species instead of hydro-mulched.
  - 3. Landscaping shall not be within the security fence.
  - 4. If landscaping is requested by a local neighborhood association, the association shall be notified that the association is responsible for the landscaping maintenance.

### 3.05 Flood Plain/Floodway

- A. Design Engineer shall design the lift station to comply with the requirements of the latest version of COH Code of Ordinance, Chapter 19 Flood Plain. Lift stations are considered critical facilities.

### 3.06 Site Drainage

- A. Adhere to stormwater drainage and mitigation requirements listed in Chapter 9 of COH Infrastructure Design Manual, latest revision.
- B. Identify and contact agency responsible for approval of stormwater facilities design, detention requirements, and discharges from site, including discharges to storm sewers or open channels.

### 3.07 Odor Control

- A. Odor control at lift stations may not be required but should be considered and addressed in the Preliminary Engineering Report. In general, odor control for City of Houston lift stations will only be required if requested by Project Manager. Odor control for non-COH lift stations will be at the discretion of the Design Engineer. The following methods and criteria should be considered as a minimum guideline.
  - 1. Chemical feed systems should be considered for new lift stations that have discharge force mains longer than 2,000 feet.
  - 2. The standard treatment for odor control is ferrous sulfate and/or calcium nitrate fed directly into the upstream manhole, lift station wet well, or force main, in that order of preference.



3. The use of activated carbon canister devices on the wet well vent pipe may be applicable.
4. Biofilter/ Bioscrubber systems can be considered for lift station odor control.

**B. Air Treatment Systems**

1. Duct work should be designed based on the following criteria.
  - a. Material of Construction
    - (1) Below Grade – Sch 80 or SDR 35 PVC, or DR 32.5 HDPE
    - (2) Above Grade – FRP coated for UV protection or 304 stainless Steel
  - b. Air Velocity – 1500 to 30,000 SCFM
  - c. Ventilation Rate – the air changes per hour should be based on NFPA 820-Fire Protection in Wastewater Treatment Plants (current edition) issued by the National Fire Protection Association but should not be less than 8-12 changes per hour.
2. Exhaust Fan
  - a. Fan should be corrosion-resistant with slide mount motor to allow sheave replacement.
  - b. Fans located outside should be noise suppressed.
  - c. Flexible connectors should be used for inlet and outlet connections.
  - d. Provide fan volute with a drain to remove liquids
3. Air Treatment Unit
  - a. Biofilter criteria shown in Table 2 are for guidance only. This criteria may be modified with appropriate engineering justification and/or manufacturer's recommendations. Please note the following design criteria is applicable for hydrogen sulfide concentrations of less than 50 ppm. Concentrations greater than 50 ppm requires lower loading rates and special consideration.

**Table 2. Biofilter Design Values**

<b>Description</b>	<b>Value</b>
Media Type	Inorganic
Air Plenum Depth	12-18 inches
Media Depth	4-6 feet
Loading Rate	12-18 cfm/ft <sup>2</sup>
Empty Bed Contact Time	20-30 seconds
Max Inlet H <sub>2</sub> S Concentration	50 ppm
Max Pressure Drop through the Media	0.25-0.33 inches wc/ ft media depth
Initial Phase pH Range	7-8.5
Media Moisture Content	40-60 % by weight
Media Porosity	40-50 %
Water Usage	10 gallons/100,000 ft <sup>3</sup> of air
Maximum Air Temperature	105
Anticipated Media Life	10-15

- b. Activated Carbon - Activated carbon canisters naturally adsorb volatile organics but may need to be specially treated to adsorb hydrogen sulfide.
  - (1) Typical bed velocities are between 50 and 75 feet per second.
  - (2) The COH will not regenerate activated carbon. The design must include provisions for carbon replacement.
  - (3) Activated carbon units are generally considered applicable for small lift stations and remote locations.

**C. Chemical Feed Systems**

1. Chemical feed systems consist of chemical storage tanks, chemical metering pump, pump calibration equipment, and associated piping and controls.
2. Provide chemical resistant motor drive diaphragm metering pumps with spare parts, calibration cylinder and corrosion-resistant pump stand. The metering pumps should have a feed rate of 1 GPH to 30 GPH and be capable of operating in manual or automatic modes.
3. Provide a panel mounted metering system with control panel, stop valve, relief valve, back-pressure valve and pressure gage.
4. House the metering pumps in a lockable FRP building equipped with lights and a GFI outlet.
5. Provide an eye wash station for the chemical feed system.
6. Design criteria for chemical feed systems are given in the table below.

**Table 3. Chemical Feed System Design Values**

<b>Parameter</b>	<b>Ferrous Sulfate<sup>(1)</sup></b>	<b>Nitrate<sup>(1)</sup></b>
Method of Chemical Delivery	Bulk Liquid	Bulk Liquid
Design Dosage	4.5 lbs FeSO <sub>4</sub> /lb DS	10 lbs NO <sub>3</sub> /lb DS
Max Allow DS at Discharge (mg/L)	<1	0.3 to 0.5
Storage Tank Capacity (days)	4-7	4-7
Storage Tank Capacity (gallons)	6500	6500
Storage Tank Material	HDPE	HDPE
Secondary Containment	Required	Required
No. of Chemical Metering Pumps	2-3	2-3

Note: <sup>(1)</sup> Feed point is above high water level in wet well or first upstream manhole.

### 3.08 Corrosion Control

- A. Design shall include consideration for corrosion protection for interior concrete surface of wet wells, structural steel and fasteners, HVAC systems, electrical, mechanical and other components that could be affected by the corrosive environment.
- B. Concrete Protection
  1. Provide corrosion protection over the entire concrete interior surface of the wet well from the bottommost extent as per the latest COH Standard Specifications and upward to include the interior surface of the top slab.
  2. PVC sheet material applied to formwork and embedded in new cast-in-place concrete structures should adhere to the latest COH Standard Specifications.
  3. Alternatively, provide polymer concrete wet wells.
- C. For chambered wet wells, provide corrosion protection via hand applied or spray-on liner systems from the COH Approved Product List.
- D. Pumps, Piping and Valve Protection
  1. Ferrous surfaces of pumps, piping and valves should be coated as described in the latest COH Standard Specifications.

## **SECTION 4: LIFT STATION HYDRAULIC DESIGN**

### **4.01 System Head and Pump Capacity Curves**

#### **A. System Head Curves**

1. Piping head losses shall be calculated in accordance with the Hydraulic Institute Standards in connection with head losses through lift station piping and valves. Appendix D includes a sample system curve calculation.
2. The Hazen-Williams “C” factors used in calculation of friction head losses should be based on the pipe material and its condition. The Design Engineer shall confirm the appropriate “C” factors over the design life of the force main and analyze system curves for the low water, high water, and flooded wet well levels.
3. The pump motors should be non-overloading over the entire range of pumping, including the ability to pump into the force main under a flooded wet well condition. For COH CIP projects, Design Engineer to coordinate the flooded wet well level with the COH project manager and IPB. The water surface elevation for the flooded condition will be the lower of lowest adjacent influent upstream manhole rim or the underside of the top slab.

#### **B. Pump Capacity Curves**

1. Pump performance curve(s) requirements should be as specified in the Design Guideline Drawings.
2. Pump curves should be plotted through the full range of operation including:
  - a. Shut-off head
  - b. Runout at lowest TDH conditions.
3. Design Engineer should select and specify pumps for the best efficiency operating point.
  - a. When two or more pumps operate together for the maximum flow condition care should be taken to insure that each pump will not operate near the shut-off or runout points. For best results, pumps should not be operated at less than 50% of the best efficiency point capacity nor be extended to beyond 120% of that capacity. This requirement may be achieved by changing the pump selection, or the force main size, or both.

- C. The Design Engineer should provide calculations confirming the  $NPSH_A$  is greater than  $NPSH_R$  as required by Hydraulic Institute to prevent cavitation.

#### 4.02 Wet Well Design

- A. Refer to Section 3.05 for wet well top of slab elevation requirements.
- B. The wet well design must allow for a flooded suction condition of the pump motor regardless of pump motor design under all operating conditions.
- C. Preferably, wet wells should have one influent sewer entering the wet well, with an upstream influent manhole on the lift station site within 100 feet of the wet well. The inflow pipe shall be straight for a length of five pipe diameters before entering the wet well. Gravity sewer from this upstream manhole to wet well shall be the next larger nominal diameter above the gravity sewer entering the influent manhole.
- D. The bottom of wet wells shall have a minimum slope of 10 percent towards the pump(s) intake and shall have a smooth finish.
- E. Size ports such that the velocity through all ports at firm capacity is greater than 4.5 fps and less than 6.5 fps.
- F. Minimum Wet Well Volume-
  1. The formula for active volume is:

$$V = \frac{T_{min} * Q_p}{4 * 7.48}$$

$T_{min}$  = Minimum cycle time in minutes

$Q_p$  = Pump capacity in gpm

$V$  = Active volume in cubic feet

2. Cycle times are referenced from the TCEQ Rules and Regulations. Refer to the table below for the minimum cycle times.

**Table 4. Design Values for Cycle Time**

Pump Size (hp)	Cycle Time (min)
< 50	6
50-100	10
> 100	15

4.03 Wet Well Levels

- A. Wet well levels for pump operation should be set to minimize the vertical drop of wastewater into the wet well. The “Lead Pump On” level shall be set below the invert of the influent sewer as to not surcharge the influent sewer.
- B. Minimum cycle times shall be accomplished without the water surface elevation (“All Pumps Off” level) dropping below the top of the pump motor.

4.04 Lift Station Bypass

- A. Provide a connection to the discharge force main to permit connection of a portable pump discharge for use in emergency conditions or lift station maintenance.
  - 1. Provide an influent manhole within the lift station site located within 100 feet of the wet well to serve as dewatering pump suction well.
  - 2. Design Engineer shall provide a bypass “Tee” and valve in a manhole on the lift station site. In cases where bypass manholes cannot be provided, provide a “Tee” and extend it up to the grating with blind flange and isolation valve on the upstream end of the header pipe in Preferred Configurations.

**SECTION 5: MECHANICAL DESIGN**

**5.01 General**

- A. This section of the Design Guidelines Manual describes procedures for designing cooling, ventilation and plumbing systems for lift stations.
- B. The wet well is a strictly unoccupied structure. The submersible pumps shall be capable of removal through the use of a rail guide removal system without the necessity of entering the structure. Pump removal by use of guide cables is not allowed.
- C. The valve vault is intended to contain isolation valves, check valves, and other appurtenances as required for a specific site. Valve vault must have adequate size and provisions for operator access and a permanently mounted access ladder or stairway. Isolation and check valves shall not be located in the wet well.
- D. Because of high ambient temperatures and heat gains from electrical equipment, the building must be provided with proper cooling to prevent overheating and possible malfunction of electrical devices.
- E. The design should comply with applicable criteria of the latest versions of TCEQ Chapter 217 and NFPA 820, Standard for Fire Protection in Wastewater Treatment and Collection Facilities.
- F. All piping from the isolation valve to discharge header should be flanged without thrust-rod tie elements.

**5.02 Pump Selection**

- A. Design Engineer shall select and specify the pumps based on the project specific requirements. Refer to Section 4: Lift Station Hydraulic Design for guidelines used in determining these pump characteristics.
- B. Design Engineer to provide life cycle cost comparisons for candidate lift station configurations. For COH CIP projects, Design Engineer to coordinate with the COH project manager for maintenance, replacement, and other criteria associated with lift stations.
- C. For COH CIP projects, it is recommended the Design Engineer include at least three different pump manufacturers and provisions for product substitutions of an “approved equal” in the specifications, in coordination with Wastewater Engineering Section and Wastewater Operations Branch.
- D. Pump selection shall include consideration of:
  - 1. Overall serviceability record of pumps

2. Cost of outside maintenance service contracts
3. Outside maintenance service performance records
4. Submersible pump power cable serviceability record and replacement costs

NOTE: The above information can be requested from COH Wastewater Operations Branch, Attn: Maintenance Group (located at 4545 Groveway Drive, Houston, TX, 77087). For COH CIP projects, Design Engineer shall coordinate with COH project manager.

### 5.03 Valves

#### A. Isolation Valves

1. Plug valves or resilient-seat, solid-wedge gate valves should be used for shut-off service in a force main application when the liquid being pumped contains gritty material.

#### B. Check Valves

1. Only full-body flanged check valves should be utilized. Wafer body valves are not acceptable for wastewater lift stations.
2. Ball-type check valves are not allowed.
3. For pump system head of 30 psi or less, the maximum velocity through a non-spring loaded or counter-weighted check valve should not exceed 3 fps. It may be increased to 5 fps for check valves which are spring loaded or counter weighted to prevent valve slamming. For pump system head higher than 30 psi, cushioned swing check valves should be used. However, cushioned swing check valves do not eliminate pressure surges when the valve closes suddenly. It only reduces the slamming noise.

#### C. Air/Vacuum Release Valves

1. The location and sizing of air/vacuum release valves along force main routes and at the lift station discharge piping shall be determined by the Design Engineer and described in the PER or Basis of Design Report.
2. Air/vacuum release valves shall be installed per the Design Guideline Drawings.

#### D. Surge Relief Valves

1. Surge relief valves are typically installed at lift stations to protect the pumps, piping, valves and other equipment from potential damage from surge pressures. If required, surge relief valves should be sized to release the excess surge flows through the valve either on the basis of system flow or so that the inlet pressure measured at the relief valve will be lower than the lowest pressure rating of the pumping equipment.



2. Surge relief valves are to be located downstream of the pump control valve/check valve or on the main discharge header as close to the pump(s) as practical. Surge relief valves typically discharge back into the wet well.
3. Consideration should be given to providing two or more, smaller sized valves having a total combined relieving capacity equal to or greater than a single larger sized valve, especially when there is more than one pump discharging into a common header. A surge relief valve may be utilized on each pump discharge line or several valves may be provided on the common discharge header.
4. When several valves are provided, it is advisable that each valve's pressure setting be slightly higher than the adjacent valve allowing the valves to open in sequence instead of all at once. It should be noted that all surge relief valves are field adjustable and their relief pressure setting range is determined when the valves are ordered from the manufacturer.

#### 5.04 Plumbing

- A. Valve vaults shall have provisions to continuously drain. The valve vault floor should be sloped toward the draining device. Based on the lift station configuration, the valve vault should be drained by two methods:
  1. For the "Preferred Low Profile" configuration, a floor drain should be provided. The floor drain should have a "P" trap and a floating ball-type backwater valve to prevent fumes and liquids from entering the vault from the wet well.
  2. For the "Alternative Low Profile" configuration, valve vaults should be equipped with a submersible electric sump pump discharging to the wet well through a check valve. The sump pump should be activated by an integral float switch.
- B. A potable water supply shall be provided for use during repairs, for washing down equipment, valve vault and grade slabs. Water should be provided through a minimum ¾ inch diameter supply line and non-freeze type hose bib located near the wet well.
- C. All water should be metered and supplied through a reduced pressure type backflow preventer for protection of the city water mains from possible contamination due to cross-connections.
- D. The above grade water supply system pipe, fitting, valves, and water meter should be insulated and protected against freezing. The complete backflow preventer assembly shall be provided with a Hot Box-type vandal proof enclosure (alternatively stainless steel or carbon steel cage painted green may be used) and equipped with access provisions for servicing and checking of the equipment.

5.05 Air Conditioning (A/C)

- A. Control Buildings house motor control centers, electrical panel's, transformers, and other equipment for operating pumps located in wet wells.
- B. The temperature in the buildings will be affected by high ambient temperatures and by heat radiated from electrical equipment. If the excess heat is not removed either with ventilation air or by mechanical cooling, the temperature in the building will rise to a point where electrical devices will malfunction and disrupt operation of the pumping station.
- C. Where clean outdoor air at suitable temperatures is available, forced ventilation is the least expensive and simplest way of removing heat from a building. Removing heat by forced ventilation should be considered when it is possible to maintain indoor temperatures not exceeding 105 degrees Fahrenheit at all times. In Houston, outdoor air may at times be very saline, and when drawn through a building, will cause corrosion and adversely affect delicate electrical instruments and devices. Therefore, controlling building temperature in such atmospheres is best accomplished by providing mechanical cooling units, where minimum or no outdoor air is circulated through the building, thus avoiding possible corrosion of equipment.
- D. The mechanical cooling units are also susceptible to corrosion from the saline atmosphere. The useful life of such units will be much shorter in a saline atmosphere than in normal atmospheric conditions. However, the operating life of mechanical units can be extended by specifying the units will be provided with a protective coating application. Heat transfer capacity of protectively coated coils is not significantly affected (normally a reduction in capacity of less than 10 percent). The coating should cover all parts that come in contact with outdoor air, which includes the casing, heat transfer coils, refrigerant tubing and electrical devices. Mechanical cooling units should be wall mounted package type, heat type, units.
- E. When sizing the cooling unit, all instantaneous sources of heat gain must be accounted. The worst scenario would be with all pumps running and the outdoor temperature 100°F, or higher, and staying within this range for a number of consecutive days. Mechanical cooling units shall be sized to maintain a building indoor temperature of 85 degrees Fahrenheit or less at a 40 percent specific humidity at maximum heat gain.
- F. Solar and transmitted heat gain calculations must be in accordance with the ASHRAE Handbook of Fundamentals. The outdoor temperature listed in the ASHRAE Guide must be adjusted for outdoor air temperature encountered in Houston, if such maximum temperature continues within that range for more than 4 hours. Maximum temperatures for the particular area must be obtained locally.
- G. Unit selection should be based on a terminal wall mounted heat pump type mechanical cooling unit having a minimum 13,000 BTUH sensible cooling capacity at 105°F outdoor air temperature at 77°F wet bulb temperature and an air temperature of 85°F dry bulb and 66°F wet bulb entering the cooling coil.

- H. The above selected unit is sized for a 4-pump system. The same unit can also be used for stations with fewer pumps and smaller heat gains.
- I. The air conditioning unit should be controlled through a room type thermostat set to maintain the room air temperature at approximately 80°F. The unit fan shall run continuously when the unit control switch is in the "on" position.

#### 5.06 Ventilation

- A. Avoid ventilation through panels because of resulting corrosion problems. Use stainless-steel panels instead of aluminum at exterior locations. All ventilation fans should be coated with corrosion-resistant material.
- B. Wet Well Ventilation
  - 1. Since the wet well is unattended and must not be entered without special provisions, a permanent type mechanical ventilation system is not required. Mechanical ventilation must be provided when the wet well is to be entered for any reason. A portable type engine or electrically driven air supply fan should be used. A quantity of outdoor air, equal to at least thirty complete air exchanges per hour of the wet well volume must be blown into the well through a flexible pipe. The point of discharge of the air into the well must be where people are present. The air supply fan must be in operation for a minimum of two minutes before anyone enters the well. Entrance hatches must be kept open to allow foul air to escape from the well while outdoor air is being blown in.
  - 2. The ventilation for a wet well should be designed as a passive gravity ventilation system (breather type), where the air volume in the well is either increased or decreased and outdoor air is pulled into the wet well and wet well air is pushed outdoors through the vent pipe, as sewage flows into or is pumped out of the wet well. The passive ventilation pipe should be sized to allow an inflow of make-up air volume to the wet well, at a rate equal to the maximum liquid pumping rate out of the wet well, with an air velocity through the vent pipe not to exceed 600 fpm. The vent size and discharge elevation should comply with the latest TCEQ requirements. In no case shall the vent pipe be less than six inches in size. Vents shall have stainless steel insect screen that is easily replaceable, prevent rain water from entering, and be corrosion-resistant.
- C. Valve Vault Ventilation
  - 1. The valve vault is normally unattended. However, on occasion it must be entered to service valves and other devices. Access shall be provided using stairways or ladders utilizing corrosion-resistant non-slip steps or rungs conforming to OSHA requirements.

2. Since odors are not normally generated in the vault, continuous ventilation and odor control are not required for valve vaults opened on top with grating and less than 15 feet in depth. There is a possibility, however, that harmful or explosive fumes may enter the vault through cracks in walls or leaking valves. For this reason, the vault must be properly ventilated before anyone enters it. Use the same ventilation requirements as described for entering wet wells.

## **SECTION 6:     STRUCTURAL DESIGN**

### **6.01    General**

- A.     This design guide describes the structural design criteria and code compliance for lift stations. The lift stations include a wet well, and may include either a control building or an outdoor control panel. The valves and discharge piping may be above grade or in a vault below ground depending on specific site requirements.

### **6.02    Design Standards**

- A.     The following codes, specifications, recommendations, allowable stresses, and loadings will be used as a minimum in designing the project structures, latest editions:
  - 1.     International Building Code (IBC) with City of Houston Amendments.
  - 2.     American Concrete Institute (ACI) 318-14: Building Code Requirements for Reinforced Concrete.
  - 3.     ACI 315: Details and Detailing of Concrete Reinforcement.
  - 4.     ACI 315R: Manual of Engineering and Placing Drawings for Reinforced Concrete Structures.
  - 5.     ACI 350R: Environmental Engineering Concrete Structures.
  - 6.     American Institute of Steel Construction (AISC) Manual of Steel Construction with updated editions.
  - 7.     American Association of State Highway and Transportation Officials (AASHTO) Standard Specifications for Highway Bridges.
  - 8.     Aluminum Design Manual, The Aluminum Association
  - 9.     Project specific Geotechnical Investigation Report.
  - 10.    Theory of Plates and Shells, by Timoshenko
  - 11.    Reinforced Masonry Design by Schneider & Dickey
  - 12.    Reinforced Masonry Engineering Handbook, by Masonry Institute of America
  - 13.    Concrete Masonry Design Tables, National Concrete Masonry Association
  - 14.    City of Houston Infrastructure Design Manual
  - 15.    Occupation Safety and Health Administration (OSHA) Publication 3124-12R 2003

16. Crane Manufacturers Association of America, Inc.

6.03 Geotechnical Coordination

- A. Refer to the project specific geotechnical design requirements prepared in accordance with the latest version of the City of Houston Infrastructure Design Manual.

6.04 Loads

A. Lift Station and Valve Vault Structures Below Grade

1. Hydrostatic liquid pressure due to maximum internal operating liquid level with no balancing external lateral pressure: 63 pounds per cubic foot (pcf)
2. Poorly draining sand or sand and gravel, lateral pressure: 80 pcf, minimum (min), or per project specific geotechnical investigation.
3. Compacted silty clay, lateral pressure: 100 pcf, min, or per project specific geotechnical investigation.
4. Top Slab at or above Grade:
  - a. Dead Load (DL): Weight of Concrete Slab
  - b. Superimposed Dead Load (SDL): Backfill or other Superimposed Dead Loads
  - c. Live Load (LL): 300 pounds per square foot (psf) or equipment weight plus 50 psf.
5. Fiber Reinforced Plastic, Aluminum cover, platform, and walkways at or below grade.
  - a. LL: 150 psf
6. Lateral load due to surcharge loading of the construction crane and HS-20 truck shall be added to loads in Sections 6.04.A.4.b and 6.04.A.4.c or per project specific geotechnical investigation.
7. All Structures shall be designed to resist buoyancy to the finished top slab.

B. Buildings and Miscellaneous Structures

1. Loadings for design of buildings to be obtained from appropriate codes. However, certain minimum loads shall be used as follows:

Minimum Uniform Live Loads:

Grating	150 psf
---------	---------

Stairs and catwalks 150 psf

Electrical control rooms 250 psf

(Estimate support area and equipment weights and assume loads applied anywhere in area in question)

Wind: As per IBC for basic wind speed = 110 mph. Exposure BB and Importance factor = 1.15

#### 6.05 Buoyancy

- A. The below grade wet wells and valve vaults will be subject to buoyant forces as defined in Section 6.04. Since a bentonite slurry may be used in the caisson excavation, the safety factor for soil friction reflects its presence. Verify that the required factors given by the geotechnical consultant are consistent with this. The structure weight shall only include the walls and slabs. The weight of fillets, baffle walls, pads, and equipment shall not be included as these could be changed in the future or may not be in place during construction.
- B. Structural design and buoyancy calculations must show a minimum Factor of Safety equal to or greater than 1.5 against Flotation (Buoyancy) for an empty structure with groundwater elevation at ground surface. The minimum Factor of Safety may be reduced based on recommendations included within a project specific geotechnical report that is sealed and signed by an engineer registered in the State of Texas, but may be no lower than 1.10. Allowances for soil friction are not allowed, unless justification included within a project specific geotechnical report sealed and signed by an engineer registered in the State of Texas provides a soil friction factor and Factor of Safety for soil friction and structural calculations are submitted by the Engineer of Record.

#### 6.06 Design Stresses

##### A. Concrete and Reinforcing Steel

##### 1. Liquid Containing Structures:

Use Strength Design Method of ACI 318,

Building Code Requirements for Reinforced Concrete, with durability factor per the latest version of ACI 350 Environmental Engineering Concrete Structures, and base crack control on a maximum Z of 115 (The minimum concrete cover for steel reinforcement shall be 4 – inches where in contact with raw sewage.)

Concrete compressive strength at 28 days  $f'_c = 4,000$  pounds per square inch (psi)

Reinforcing steel (A 615, Gr. 60)  $f_y = 60,000$  psi

2. Building and Non-Liquid Containing Structures:

Use Strength Design Method of ACI 318

Concrete compressive strength at 28 days  $f'_c = 4,000$  psi

Reinforcing steel (A 615, Gr. 60)  $f_y = 60,000$  psi

B. Structural Steel

1. Follow AISC Specification for the Design, Fabrication and Erection of Structural Steel for Building, latest edition, and use following materials:

- a. ASTM A36 unless otherwise specified
- b. ASTM A325 H.S. bolts
- c. ASTM A449 OR F1554 or A36 bar stock for anchor bolts

6.07 Design Considerations

A. Wet Well Load Cases:

- 1. Wet well empty with full lateral exterior load.
- 2. Wet well filled to the maximum level possible during a power outage, while disregarding exterior soil pressures.
- 3. Wet well buoyancy when wet well shell is empty, absent any equipment or metal components and ground water elevation set at adjacent ground surface.

B. Differential Soil Movement:

- 1. Due to the significant difference in foundation elevations between the wet well and the valve slab or vault, there is a potential for differential soil movement resulting from settlement, expansive clays, or movement needed to develop soil friction. This potential movement is most severe where wet wells are constructed by the caisson method. The open cut construction method allows for placing cement-stabilized sand so as to minimize the movement potential. The Design Guideline Drawings include expansion or rotation joints.

C. Wet Well Design:

- 1. Pre-cast manhole risers and reinforced concrete pipes (RCP) are not acceptable for wet well design/construction; except for ASTM C76, Class IV Wall C, RCP, 6-foot diameter wet wells, less than 30-feet deep.



2. The circular wet well shall be designed using a recognized shell theory or by using the Portland Cement Association publication, "Circular Concrete Tanks without Prestressing."
3. The Design Guideline Drawing indicates dowels connecting the wall to the base slab for the caisson construction method. Structural connections between base slab and caisson shall be designed to transfer full base reactions from slab to wall. Full base reactions are:
  - a. For downward load: weight of components supported on the slab plus the weight of liquid at maximum elevation in the wet well;
  - b. For upward load: (1) soil bearing reactions; and (2) hydrostatic uplift pressures, together with any potential soil uplift pressure caused by instability, for empty well. Hydrostatic pressure shall be as defined in Section 6.04, Soil Uplift Pressures shall be based on geotechnical analysis.
4. Wall Base Cutting Shoe Details
  - a. The minimum depth of the cutting shoe base below the final excavation bottom shall be shown on the drawings. The required depth to maintain bottom stability shall be based on geotechnical analysis. In no case shall the required minimum depth of shoe penetration below the final excavation bottom be less than 1.5-feet.
  - b. Under no circumstances shall the excavation depth shown on the drawings require excavation below the top of the inside bevel of the cutting shoe.

D. Additional Stresses Due to Caisson Construction:

1. Caisson and/or Open Cut types of construction should be designed and shown on the drawings.
2. Tilting or out of plumbness may occur during sinking of caisson. Tilting shall be not more than 1-inch per 5-foot depth of caisson. Tilting causes bending stresses in the caisson wall. These additional stresses shall be included in the design of caisson wall.
3. Sudden sinking causes axial tension in caisson wall. When frictional and adhesion forces on upper length of caisson are equal to total weight of caisson, caisson sinking stops. This stoppage causes hang-up forces resulting in axial tension in caisson wall. Minimum hang-up force equal to one half the weight of caisson shall be used in design of longitudinal reinforcement in caisson wall.

E. Control Building Design

1. Follow the recommendations of the geotechnical report for the type and depth of the foundation.

2. Verify structural design of the Control Building included in the Design Guideline Drawings for compliance with applicable building codes and permitting requirements.

**F. Valve Vaults**

1. Access shall be provided to underground valve vaults. Stairways shall have corrosion-resistant, non-slip steps and conform to OSHA regulations.
2. Access over pipes, which extend to greater than 30-inches above the floor, shall be as detailed in the Design Guideline Drawings.
3. Use of vault-type or above ground valves and piping is permitted. Valves shall be mounted in a concrete vault, or on an above ground concrete foundation.
4. The dimensions of the valve vaults associated with each standard configuration shall be based on OSHA standard clearances for entrance ladders, piping, valves, and walls or beams.
5. Minimum vertical distance from valve vault floor or grate walking surface to bottom of top slab or beam equals 6 feet - 8 inches minimum.

**6.08 Detailing**

- A. Detailing of the reinforcement shall follow the requirements of the latest version of ACI 315, ACI 315R, ACI 318, and ACI 350R.
- B. All construction joints in water containing and below grade elements shall be provided with a 6-inch PVC water stop. All expansion joints shall be provided with a minimum 9-inch PVC center bulb water stop and shall extend the full width of wall. Where construction requirement or joint geometry will not allow a 6-inch PVC water stop, a surface applied water stop which forms a positive seal by adhesion or expanding in the presence of water may be used. Notes and/or details shall be added to insure that all joints and joint intersections are continuously sealed.

**6.09 Handrails**

- A. Provide 3-rail type handrails as indicated in Design Guideline Drawings. Handrails shall comply with OSHA and IBC requirements and be designed to sustain a 200-pound load in any direction.
- B. Handrails must provide an adequate handhold to grasp and prevent falls.
- C. Aluminum or UV-stabilized Fiberglass handrails may be used.
- D. Fiberglass gratings and handrails must be UV-stabilized for exterior use to prevent their significant deterioration resulting from extensive ultraviolet exposure.

- E. Provide storage spaces along the wall inside the control building for all removable handrail sections. Provide stainless steel tieback chains to prevent units from falling.
- F. Coordinate spacing of stanchions and concrete insert anchors to minimize the number of different handrail section configurations required. Provide removable sections sufficient to guard at least three hatch openings.

## **SECTION 7: ELECTRICAL DESIGN**

### **7.01 Design Standards**

- A. Design electrical systems in conformance with the National Electrical Code (NEC) as adopted by the City.
- B. Design electrical systems in conformance with the City of Houston Building Code.
- C. Design facilities in accordance with National Fire Protection Association (NFPA) 820 for ventilation according to NEC area hazardous classification requirements.
- D. Design lightning protection in accordance with NFPA 780.
- E. Design lighting system in accordance with Illuminating Engineering Society (IES) handbook.

### **7.02 Basis of Design**

- A. Prior to assembling a drawing package, the following site specific data must be established and calculations performed. Refer to the current applicable Design Guideline Drawings for Submersible Lift Stations as the basis for design.
  - 1. Number and size of pumps (gpm & HP/KW)
  - 2. Lift Station configuration (Preferred, Alternate Low, Alternate High lift station configuration).
  - 3. Location of electrical junction box(s) above grade or in valve vault
  - 4. For projects within the ETJ area, the City owned and operated WiMAX wireless communication radio may be replaced by Auto dialer for remote alarm notifications. The control system for the station shall remain unchanged. Refer to the latest Design Guideline Drawings. This design document is to be used for all lift stations as a basis for designs within the City of Houston and ETJ area.
  - 5. Fencing requirements
  - 6. Manual transfer switch system for alternate power distribution in emergency.
  - 7. Full load calculations
  - 8. Provide motor starting analysis and maximum short circuit calculations. List maximum short circuit amperage on the drawings and specify the method of calculation. (i.e. point to point or IEEE)

9. Design Engineer shall specify the Contractor to provide Power System Study and arc fault labeling according to NEC 110.24. The Power System Study specification section shall be included with the construction bid documents.
- B. Approval of designs for ETJ lift station control system packages serving utility districts in the ETJ shall be allowed if one or more of the following conditions are met:
  1. The district where the lift station is located has a minimum of 15 years remaining under an executed Strategic Partnership Agreement with the City of Houston,
  2. The project includes a temporary lift station at a wastewater treatment plant,
  3. The project includes a temporary lift station while the permanent lift station is under rehabilitation, or construction,
  4. The plans show future expansion of the City of Houston lift station control system package.
  5. The Owner has executed an agreement with the City of Houston stating the area being served by the lift station location will not be annexed.
  6. The Owner has executed an agreement with the City of Houston with a term not to exceed 15 years, stating that the lift station electrical controls will be upgraded before annexation to the future current design criteria and the Owners shall, subject to the availability of funds from a legally available source, pay for those upgrades without extending the term of the outstanding the indebtedness of the Owner.

#### 7.03 Electrical Drawing Set

- A. Each design package shall contain the following minimum electrical drawings:
  1. Electrical Symbols Legend, Lighting Fixture Schedule & Abbreviations
  2. Site Plan, including grounding and outdoor yard lighting around the property
  3. Power and Control Rack Plan and Details
  4. Underground Conduit Routing Plan
  5. Underground Conduit Section Details
  6. Electrical Design Details
  7. Control Building Plan and details (for sites with control buildings)
  8. Control Cabinet Enclosure

9. Control Cabinet Elevation
  10. Control Cabinet Equipment Layout and Schedule
  11. Process and Instrumentation Diagram
  12. Control System Wiring Diagrams
  13. MCC & PLC Power Schematic Wiring
  14. Communication Diagram
  15. Single Line Diagram
  16. Cable and Conduit Schedule
  17. Device Rating Schedule
  18. MCC Elevation (for sites with a building)
- B. The electrical drawing set is arranged with a control system and instrumentation for packages up to 6 pumps. The electrical and instrumentation are designed as packages to correspond with the civil, structural, mechanical, and electrical drawings for lift station configuration series A to N (refer to the latest Design Guideline Drawings for Submersible Lift Stations).
1. Eight electrical and control system packages were developed for configurations sized from 2-125 HP ratings providing control panels and buildings sized adequately to house all equipment.
    - a. Control System Package Types
      - (1) 2 Pump Constant Speed Indoor and Outdoor
      - (2) 3 Pump Constant Speed Indoor and Outdoor
      - (3) 4 Pump Constant Speed Indoor and Outdoor
      - (4) 5 Pump Constant Speed Indoor
      - (5) 5 Pump Constant Speed Indoor (3 Wet Weather and 2 Dry Weather)
      - (6) 6 Pump Constant Speed Indoor
      - (7) 6 Pump Constant Indoor (4 Wet Weather and 2 Dry Weather)
      - (8) 6 Pump Variable Frequency Drive (VFD)

7.04 Indoor Electrical Symbols, Legend, Lighting Fixture Schedule & Abbreviations Sheet

- A. This sheet defines the symbols and abbreviations utilized in the preparation of the contract drawing package, and schedules the lighting fixtures used. Prepare this sheet for the site specific requirements using the Design Guide line drawing as a basis for design.
- B. Include this sheet in each design package. Do not delete symbols or abbreviations from this sheet. Add any special items used in preparation of the final package. Delete any lighting fixtures not applicable.

7.05 Site Plan

- A. In addition to the Design Guideline Drawings required, a site specific electrical site plan shall be created. After attaining the basic civil site plan, the following electrical information shall be established and/or added:
  - 1. Locate the electrical building or electrical panel in accordance with the COH latest Design Guidelines.
  - 2. Locate the electrical service entrance point.
  - 3. Orient the electrical plans to coincide with the civil plans.
  - 4. Route conduits from electrical service and communication pole locations to the control building/cabinet.
  - 5. Locate all yard lights (preferred one at each corner of property) and route conduit from control building/cabinet. Provide a manual light switch for perimeter lights and inside the building or control panel. The light mounted on the WiMAX pole shall operate via photo sensor.
  - 6. Establish site grounding and provide ground connections for service entrance, control building/cabinet, handrails, above grade electrical junction boxes, yard lights, piping and all metal parts of fencing and entrance gate.
- B. Note: An example of a typical electrical site plan is included in the Design Guideline Drawing packages as referenced material for the Design Engineer. Do not include this drawing in the project drawing package without site specific modifications.

7.06 Electrical Plans and Sections

- A. From the Design Guideline Drawings, select drawings for the appropriate lift station configuration and size. Review all drawings and details and revise to accommodate specific site and facility requirements. Design Engineer shall review and remove all notes referenced to Design Engineer. Refer to Appendix E for an example of the note removal. At a minimum, the following review and revisions are required:

1. Verify structural dimensions of the valve vault and the wet well. Revise the electrical plans accordingly.
2. Provide quantities and locations of level transmitters, sensors and instrumentation interface system as required per package used.
3. Verify drawing number cross references for section callouts.
4. Verify all sections referenced are included in the document set.
5. Verify all electrical details conform to the latest NEC requirements.
6. Orient electrical plans and conduit layout sheets to correspond with the site plan.
7. Adjust north arrow on each plan sheet according to the site north.
8. Add any special or extra features required at this specific site. Do not use conduits designated as "future space" for undesignated additions.
9. Provide power factor correction capacitors per COH latest Design Guideline Drawings for horse power requirements (20 HP and greater) and specify location on the drawings. Connect capacitors to the motor starter leads ahead of the motor overload relay. Exercise caution to specify capacitors with over-current fuses and indicating lights. Locate capacitors adjacent to the motor controller and terminate according to the NEC Article 240-21.

#### 7.07 Typical Details

- A. The typical electrical details are to be revised and combined as necessary to meet specific site conditions. The latest Design Guideline Drawings includes a manual transfer switch for portable generator connection per TCEQ chapter 217. In general, the details are located in drawing series X (outdoor control panel), Y (indoor control panel), and Z (details apply to both outdoor and indoor drawing sheets). Refer to list of drawings per latest Design Guideline Drawings for Submersible Lift Stations.

#### 7.08 Control Building Plan

- A. Include this sheet in each lift station package with a control building. Revise building dimensions, number of MCC sections, utility service and conduit plan based on the specific lift station configuration and size (control building dimensions as shown on the Device Rating Schedules drawing). Orient the building plans and add a north arrow to coordinate with the site plan. Revise lightning protection details to coordinate with actual building construction and materials. Relocate alarm light to provide visibility from access road.



7.09 Control Cabinet Layout

- A. Based on the size of the station and the intended location of the control cabinet (indoor or outdoor), select the appropriate control package from the latest Design Guideline Drawings. Revise the dimensions, elevation, and device layout based on the actual number of pumps. The outdoor power and control cabinets are shown back-to-back in a single four door enclosure. For installations where this approach is not feasible, the designer shall separate the two sections (shown as the front control panel and the back power panel), adjust enclosure depth, and provide interconnecting wiring required for the number of pumps used.

7.10 Process and Instrumentation Diagrams

- A. Based on the number of pumps and system configuration, select the appropriate process and instrumentation diagrams (P&ID). Revise P&ID based on number of pumps.

7.11 Control System Wiring Diagrams

- A. Based on the number of pumps and system configuration, select the appropriate control system package.

7.12 Wireless Communication and Site Monitoring Equipment

- A. Wireless communication and site monitoring equipment is required for all lift station configurations. Refer to applicable Design Guideline Drawings for detailed design.

7.13 MCC & Power Wiring Diagram

- A. Select the appropriate diagram and revise to reflect actual number of pumps, valve vault exhaust fans, service voltage, and other site specific conditions.

7.14 Single Line Diagrams

- A. Based on the location of the motor controls, select the appropriate diagram. Revise the selected single line diagram to reflect actual number of pumps, service voltage, use of a valve vault, use of a lighting transformer, etc. Coordinate service entrance voltage, transformer rating/type, fault current, and metering requirements with utility service provider.

7.15 Conduit Schedule

- A. Prepare a project specific conduit schedule with the following columns from the appropriate Design Guideline Drawing:
  - 1. Conduit Number
  - 2. Description

3. Service (Voltage, Amps, and HP)
  4. Routing (From, To, Via)
  5. Conduit, Cable or Wire Sizes
- B. Revise the table to provide conduit and wire sizes and descriptions in accordance with NEC requirements for actual site conditions. Conduits not necessary at a specific site should be deleted from the schedule. Show conduits to be installed for future use as "Installed Spare" or "Future Space" on the Schedule.
- C. Notes to the Design Engineer are provided to assist the designer in selecting conduits for certain special installations. Revise the conduit schedule selected based on the appropriate notes. Delete the notes from the final document.

#### 7.16 Device Ratings Schedule

- A. Prepare a site specific device ratings schedule by including the following columns from the appropriate sheets:
1. Item
  2. Circuit
  3. Description
  4. Rating (Select the column that corresponds to the actual pump rating.)
- B. All pump sizes are specified in standard motor horsepower. For submersible pumps that do not precisely correspond with standard horsepower, select the next higher horsepower.
- C. Verify that device ratings selected are in accordance with current NEC specified requirements.

#### 7.17 MCC Elevations (Drawing View)

- A. For projects that include a MCC, include the MCC elevation view specified on the device rating schedule from the Design Guideline Drawings for the appropriate number of pumps, and horsepower ratings required.

## **SECTION 8:      FORCE MAIN DESIGN**

### **8.01    Sizing Limitations**

- A.    Refer to TCEQ Rules and Regulations, latest version, for minimum force main size.
- B.    Dual force mains should be evaluated and considered for lift stations with large flow variations resulting from wet weather events. One force main should be considered to handle wet-weather flow either singularly or in parallel with the dry-weather force main.

### **8.02    Flow Velocity**

- A.    Design Engineer must provide calculations that establish low and high flow force main velocities. COH design criteria for normal force main applications are a minimum velocity of 3 feet per second (fps) for lift stations with two pumps with one pump in operation. For a lift station with three or more pumps, the minimum velocity in a force main is 3 fps with only the smallest pump operating at full speed, and a minimum flushing velocity of 5 fps or greater occurring in the force main at least twice in a 24-hour period. Velocity in force mains shall not exceed 8 fps at any time.
- B.    The PER and Basis of Design Report must certify that a pipeline with a velocity greater than 6 fps can withstand high and low negative surge pressures in the event of sudden pumping system failure.

### **8.03    Detention Time**

- A.    Force mains shall be designed to minimize detention times.
- B.    Per TCEQ Chapter 217, force main detention calculations must be performed using a range of flow rates that represent the flows expected to be delivered to a force main by the upstream lift station during any 24-hour period.

### **8.04    Alignment Criteria**

- A.    Refer to COH Infrastructure Design Manual (IDM), latest revision, for minimum horizontal and vertical clearance requirements.

### **8.05    Discharge Manhole**

- A.    For force mains discharging to manholes, the force main invert elevation should match that of the manhole invert. Force mains entering manholes above the manhole invert shall enter through an internal manhole drop structure per COH Standard Drawings.
- B.    Force main discharges should be designed to minimize turbulence and, thus, hydrogen sulfide and odor stripping. A new manhole receiving a force main discharge must be specified and shown on the drawings as a "corrosion-resistant manhole". Refer to COH Standard Drawing, "Corrosion Resistant Manhole for Force Main Discharge."

8.06 Pipe Material

- A. Refer to the COH Standard Specification “Sanitary Sewer Force Mains”, latest version, for piping material requirements.

8.07 Water Hammer and Surge Analysis

- A. Rapid changes in flow can lead to pipe pressure upsurges or downsurges that can cause rupture or water column separation and collapse of pipe. Refer to Section 5.03 for surge relief valve requirements at lift stations.
- B. Force main design shall include effective surge control measures to manage pressure due to water hammer that may exceed the working strength of the pipeline. Surge pressure control shall be addressed in the PER.

8.08 Force Main Pipe Valves and Drains

- A. Low points in a force main should be provided with a blow-off valve, especially when the sewage contains grit and other inorganic solids and the pipe slopes of the falling and rising legs are steep. The blow-off liquid may be drained to a nearby gravity sewer or be removed by a tank truck.
- B. A blow-off valve should be installed between isolation valves on force mains for maintenance and repairs. TCEQ requires isolation valves to be placed at least every 2,000 feet. Isolation valves shall be installed at the downstream side of air release valves when possible. Valves shall be of a non-clog design and suitable for use in highly corrosive environments, internally and externally.
- C. Blow-off valves should be a minimum size of 4-inches. The Design Engineer shall provide calculations to size the blow-off valve.

8.09 Downstream Hydraulic Capacity

- A. Gravity sewers receiving force main discharge flows shall have sufficient capacity to operate, without surcharging, to handle flows from the force main and any other discharges entering at or upstream of the point of force main discharge. For COH CIP projects, Design Engineer shall coordinate with IPB to determine the hydraulic capacity of the collection system downstream of the force main discharge.

**APPENDIX A – DESIGN GUIDELINE DRAWING SHEET LIST**


(Note: The referenced drawings can be downloaded from the City of Houston Website)

City Of Houston

Design Guideline Drawings  
For Submersible Lift Stations  
Filename & Sheet Numbering Designation Codes

Description			Maximum Firm
Code	Station Configuration	Pump Size Range	Station Capacity
A	2-Pump Station	0-199 gpm Per Pump	199 gpm
B	2-Pump Station	200-499 gpm Per Pump	499 gpm
C	2-Pump Station	500-999 gpm Per Pump	999 gpm
D	3-Pump Station	250-500 gpm Per Pump	1000 gpm
E	3-Pump Station	500-999 gpm Per Pump	1998 gpm
F	3-Pump Station	1000-1399 gpm Per Pump	2798 gpm
G	3-Pump Station	1400-1999 gpm Per Pump	3998 gpm
H	3-Pump Station	2000-3499 gpm Per Pump	6998 gpm
I	4-Pump Station	500-2500 gpm Per Pump	7500 gpm
J	4-Pump Station	800-3499 gpm Per Pump	10497 gpm
K	5-Pump Station	2500-3999 gpm Per Pump	15996 gpm
L	5-Pump Station	3 Wet & 2 Dry Weather Pumps	
M	6-Pump Station	3000- 5299 gpm Per Pump	26495 gpm
N	6-Pump Station	4 Wet & 2 Dry Weather Pumps	
O	6-Pump VFD Station	Conduit Layout	
P	Open		
Q	Open		
R	Open		
S	Open		
T	Open		
U	Open		
V	Open		
W	Open		
X	2, 3, & 4 Pump Station	Outdoor Control Cabinet & Wiring	
Y	All Pump Stations	Indoor Control Cabinet & Wiring	
Z	All Pump Stations	Common Drawings	

Filename Designation



Discipline Codes

- A – Architectural
- C – Civil
- E – Electrical & Instrumentation
- G – General
- S – Structural

Configuration Codes

- 0 – Dwg Non–Specific to Configuration
- 1 – Alternate High Profile Configuration
- 2 – Preferred Configuration
- 3 – Alternate Low Profile Configuration

NOTES TO DESIGN ENGINEER:

A. THESE LIFT STATION DRAWINGS ARE CONSIDERED TO BE DESIGN GUIDELINES FOR THE CONSTRUCTION OF CITY OF HOUSTON WASTEWATER SUBMERSIBLE LIFT STATIONS. THEIR INTENDED USE IS AS A FRAMEWORK FOR THE CONTRACTED DESIGN ENGINEER IN DEVELOPING SPECIFIC LIFT STATION DESIGNS. IT IS THE RESPONSIBILITY OF THE CONTRACTED DESIGN ENGINEER TO VERIFY THE COMPLETENESS AND ACCURACY OF THE INFORMATION HEREIN CONTAINED AND TO ADJUST ACCORDING TO SPECIFIC SITE REQUIREMENTS.

B. FOUNDATION REINFORCING SHOWN IS BASED ON SOIL BEARING PRESSURE OF 2000 psf. DESIGN ENGINEER SHALL VERIFY AND ADJUST AS REQUIRED FOR SITE SPECIFIC GEOTECHNICAL RECOMMENDATIONS

C. DESIGN ENGINEER SHALL SELECT THE APPROPRIATE BUILDING LENGTH, MCC CONFIGURATION AND CONTROL PANEL WIDTH (SEE DEVICE RATINGS SCHEDULES ON SHEETS 20E40 THRU 20E44), AND SHALL ADJUST THE FLOOR PLAN (SECTION A1A) AND THE SIDE ELEVATION (VIEW A1D) ACCORDINGLY. SEE SHEET 20E05 FOR ALTERNATE LOCATION OF TRANSFORMER AND LIGHTING PANEL IF REQUIRED, SEE SHEETS 20E40 THRU 20E44.

D. DESIGN ENGINEER SHALL PROVIDE A NORTH ARROW ADJACENT TO THE FLOOR PLAN (SECTION A1A).

E. THE DESIGN ENGINEER SHALL VERIFY THE STRUCTURAL ADEQUACY OF THE BUILDING DESIGN, AND SHALL COMPLETE NOTE NO. 6 PROVIDING THE APPROPRIATE DESIGN CRITERIA USED FOR THIS VERIFICATION.

F. THE DESIGN ENGINEER SHALL DESIGN ROOF TIMBER TRUSSES IN ACCORDANCE WITH SECTION 3 OF THE ENGINEERING DESIGN MANUAL AND THE CITY OF HOUSTON TECHNICAL SPECIFICATIONS SECTION 06193 – PLATE CONNECTED WOOD TRUSSES.

G. THE DESIGN ENGINEER SHALL INCORPORATE ONLY THE NECESSARY STANDARD GUIDELINE DRAWINGS AND DETAILS INTO HIS PROJECT CONTRACT DOCUMENTATION PACKAGE, AND SHALL ADJUST PAGE NUMBERS AND CROSS REFERENCING ACCORDINGLY.

H. THE DESIGN ENGINEER SHALL CONSULT THE CITY OF HOUSTON DESIGN GUIDELINES MANUAL, THE ENGINEERING DESIGN MANUAL, AND THE MASTER SPECIFICATIONS FOR FURTHER INSTRUCTIONS AND INFORMATION PERTINENT TO THESE STANDARD DESIGN GUIDELINE DRAWINGS.

I. THE DESIGN ENGINEER SHALL REMOVE THESE NOTES, ALL REFERENCES TO THESE NOTES, AND ANY OTHER EXTRANEOUS INFORMATION FROM THE DESIGN GUIDELINE DRAWINGS. DESIGN ENGINEER SHALL PROVIDE ANY NOTES OR OTHER APPROPRIATE INFORMATION NECESSARY TO COMPLETE THE LIFT STATION DESIGN.

NOTES:

FILE NAME & SHEET  
NUMBERING DESIGNATION CODE  
SHEET 1 OF 1

PROJECT NO.  
R-0267-02-2

TITLE  
CITY OF HOUSTON  
DESIGN GUIDELINE DRAWINGS  
FOR SUBMERSIBLE LIFT STATIONS

CITY OF HOUSTON  
DEPARTMENT OF PUBLIC WORKS AND ENGINEERING  
ENGINEERING, CONSTRUCTION AND REAL ESTATE GROUP

APPROVALS

WATER DESIGN

TRAFFIC AND SIGNAL DESIGN

STORM SEWER DESIGN

STREET, BRIDGE & R.O.W.

WASTEWATER DESIGN

CONSTRUCTION

OTHER REVIEWS

PLANNING AND DEVELOPMENT

CITY ENGINEER

DATE

SCALE: AS NOTED

DESIGNED BY:

SUBMITTED:

DRAWN BY:

DATE:

SHEET NO. OF SHEETS

SURVEY BY:

DWG. NO.

REV. NO.

DESCRIPTION

APP'D

DATE

FIELD BOOK NO.


LEGEND

City Of Houston

Design Guideline Drawings  
For Submersible Lift Stations  
Filename & Sheet Numbering Designation Codes

Description			Maximum Firm
Code	Station Configuration	Pump Size Range	Station Capacity
A	2-Pump Station	0-199 gpm Per Pump	199 gpm
B	2-Pump Station	200-499 gpm Per Pump	499 gpm
C	2-Pump Station	500-999 gpm Per Pump	999 gpm
D	3-Pump Station	250-500 gpm Per Pump	1000 gpm
E	3-Pump Station	500-999 gpm Per Pump	1998 gpm
F	3-Pump Station	1000-1399 gpm Per Pump	2798 gpm
G	3-Pump Station	1400-1999 gpm Per Pump	3998 gpm
H	3-Pump Station	2000-3499 gpm Per Pump	6998 gpm
I	4-Pump Station	500-2500 gpm Per Pump	7500 gpm
J	4-Pump Station	800-3499 gpm Per Pump	10497 gpm
K	5-Pump Station	2500-3999 gpm Per Pump	15996 gpm
L	5-Pump Station	3 Wet & 2 Dry Weather Pumps	
M	6-Pump Station	3000- 5299 gpm Per Pump	26495 gpm
N	6-Pump Station	4 Wet & 2 Dry Weather Pumps	
O	6-Pump VFD Station	Conduit Layout	
P	Open		
Q	Open		
R	Open		
S	Open		
T	Open		
U	Open		
V	Open		
W	Open		
X	2, 3, & 4 Pump Station	Outdoor Control Cabinet & Wiring	
Y	All Pump Stations	Indoor Control Cabinet & Wiring	
Z	All Pump Stations	Common Drawings	

Filename Designation



Discipline Codes

- A – Architectural
- B – Civil
- E – Electrical & Instrumentation
- G – General
- S – Structural

Configuration Codes

- 0 – Dwg Non-Specific to Configuration
- 1 – Alternate High Profile Configuration
- 2 – Preferred Configuration
- 3 – Alternate Low Profile Configuration

NOTES TO DESIGN ENGINEER:

A. THESE LIFT STATION DRAWINGS ARE CONSIDERED TO BE DESIGN GUIDELINES FOR THE CONSTRUCTION OF CITY OF HOUSTON WASTEWATER SUBMERSIBLE LIFT STATIONS. THEIR INTENDED USE IS AS A FRAMEWORK FOR THE CONTRACTED DESIGN ENGINEER IN DEVELOPING SPECIFIC LIFT STATION DESIGNS. IT IS THE RESPONSIBILITY OF THE CONTRACTED DESIGN ENGINEER TO VERIFY THE COMPLETENESS AND ACCURACY OF THE INFORMATION HEREIN CONTAINED AND TO ADJUST ACCORDING TO SPECIFIC SITE REQUIREMENTS.

B. FOUNDATION REINFORCING SHOWN IS BASED ON SOIL BEARING PRESSURE OF 2000 psf. DESIGN ENGINEER SHALL VERIFY AND ADJUST AS REQUIRED FOR SITE SPECIFIC GEOTECHNICAL RECOMMENDATIONS

C. DESIGN ENGINEER SHALL SELECT THE APPROPRIATE BUILDING LENGTH, MCC CONFIGURATION AND CONTROL PANEL WIDTH (SEE DEVICE RATINGS SCHEDULES ON SHEETS 20E40 THRU 20E44); AND SHALL ADJUST THE FLOOR PLAN (SECTION A1A) AND THE SIDE ELEVATION (VIEW A1D) ACCORDINGLY. SEE SHEET 20E05 FOR ALTERNATE LOCATION OF TRANSFORMER AND LIGHTING PANEL IF REQUIRED, SEE SHEETS 20E40 THRU 20E44.

D. DESIGN ENGINEER SHALL PROVIDE A NORTH ARROW ADJACENT TO THE FLOOR PLAN (SECTION A1A).

E. THE DESIGN ENGINEER SHALL VERIFY THE STRUCTURAL ADEQUACY OF THE BUILDING DESIGN, AND SHALL COMPLETE NOTE NO. 6 PROVIDING THE APPRPPRIATE DESIGN CRITERIA USED FOR THIS VERIFICATION.

F. THE DESIGN ENGINEER SHALL DESIGN ROOF TIMBER TRUSSES IN ACCORDANCE WITH SECTION 3 OF THE ENGINEERING DESIGN MANUAL AND THE CITY OF HOUSTON TECHNICAL SPECIFICATIONS SECTION 06193 – PLATE CONNECTED WOOD TRUSSES.

G. THE DESIGN ENGINEER SHALL INCORPORATE ONLY THE NECESSARY STANDARD GUIDELINE DRAWINGS AND DETAILS INTO HIS PROJECT CONTRACT DOCUMENTATION PACKAGE, AND SHALL ADJUST PAGE NUMBERS AND CROSS REFERENCING ACCORDINGLY.

H. THE DESIGN ENGINEER SHALL CONSULT THE CITY OF HOUSTON DESIGN GUIDELINES MANUAL, THE ENGINEERING DESIGN MANUAL, AND THE MASTER SPECIFICATIONS FOR FURTHER INSTRUCTIONS AND INFORMATION PERTINENT TO THESE STANDARD DESIGN GUIDELINE DRAWINGS.

I. THE DESIGN ENGINEER SHALL REMOVE THESE NOTES, ALL REFERENCES TO THESE NOTES, AND ANY OTHER EXTRANEOUS INFORMATION FROM THE DESIGN GUIDELINE DRAWINGS. DESIGN ENGINEER SHALL PROVIDE ANY NOTES OR OTHER APPROPRIATE INFORMATION NECESSARY TO COMPLETE THE LIFT STATION DESIGN.

NOTES:

FILE NAME & SHEET NUMBERING DESIGNATION CODE SHEET 1 OF 1	
PROJECT NO. R-0267-02-2	
TITLE CITY OF HOUSTON DESIGN GUIDELINE DRAWINGS FOR SUBMERSIBLE LIFT STATIONS	
CITY OF HOUSTON DEPARTMENT OF PUBLIC WORKS AND ENGINEERING ENGINEERING, CONSTRUCTION AND REAL ESTATE GROUP	
APPROVALS	
WATER DESIGN	TRAFFIC AND SIGNAL DESIGN
STORM SEWER DESIGN	STREET, BRIDGE & R.O.W.
WASTEWATER DESIGN	CONSTRUCTION
OTHER REVIEWS	
PLANNING AND DEVELOPMENT	
CITY ENGINEER	DATE
SCALE: AS NOTED	DESIGNED BY:
SUBMITTED:	DRAWN BY:
DATE:	SHEET NO. OF SHEETS
SURVEY BY:	DWG. NO.
REV. NO.	FIELD BOOK NO.
LEGEND	

SEAL

CADD DWG. FILE NO. :  
FILENAME.DWG (Scale: ###)

COHSTD.BDR

0 1 2 3

ORIGINAL SCALE IN INCHES  
FOR REDUCED PLANS

REV. NO.	DESCRIPTION	APP'D	DATE







I SERIES (500-2500 GPM)

Alternate High Profile Configuration

Drawing No.

Title

I1C01

Plan View @ Grade - 4 Pumps @ 500-2500 GPM Per Pump

I1C02

Elevation Section - 4 Pumps @ 500-2500 GPM Per Pump

I1C03

Base Section - 4 Pumps @ 500-2500 GPM Per Pump

I1S01

Structural - 4 Pumps @ 500-2500 GPM Per Pump

I1S02

Structural - 4 Pumps @ 500-2500 GPM Per Pump

I1S03

Structural - 4 Pumps @ 500-2500 GPM Per Pump

Preferred Configuration

Drawing No.

Title

I2C01

Plan View @ Grade - 4 Pumps @ 500-2500 GPM Per Pump

I2C02

Elevation Section - 4 Pumps @ 500-2500 GPM Per Pump

I2C03

Base Section - 4 Pumps @ 500-2500 GPM Per Pump

I2S01

Structural - 4 Pumps @ 500-2500 GPM Per Pump

I2S02

Structural - 4 Pumps @ 500-2500 GPM Per Pump

I2S03

Structural - 4 Pumps @ 500-2500 GPM Per Pump

I2S04

Structural - 4 Pumps @ 500-2500 GPM Per Pump

Alternate Low Profile Configuration

Drawing No.

Title

I3C01

Plan View @ Grade - 4 Pumps @ 500-2500 GPM Per Pump

I3C02

Elevation Section - 4 Pumps @ 500-2500 GPM Per Pump

I3C03

Base Section - 4 Pumps @ 500-2500 GPM Per Pump

I3S01

Structural - 4 Pumps @ 500-2500 GPM Per Pump

I3S02

Structural - 4 Pumps @ 500-2500 GPM Per Pump

I3S03

Structural - 4 Pumps @ 500-2500 GPM Per Pump

I3S04

Structural - 4 Pumps @ 500-2500 GPM Per Pump

M SERIES (3000-5299 GPM)

Alternate High Profile Configuration

Drawing No.

Title

M1C01

Plan View @ Grade - 6 Pumps @ 3000-5299 GPM Per Pump

M1C02

Elevation Section - 6 Pumps @ 3000-5299 GPM Per Pump

M1C03

Base Section - 6 Pumps @ 3000-5299 GPM Per Pump

M1C04

Station Operation Tables - 6 Pumps @ 3000-5299 GPM Per Pump

M1S01

Structural - 6 Pumps @ 3000-5299 GPM Per Pump

M1S02

Structural - 6 Pumps @ 3000-5299 GPM Per Pump

M1S03

Structural - 6 Pumps @ 3000-5299 GPM Per Pump

Preferred Configuration

Drawing No.

Title

M2C01

Plan View @ Grade - 6 Pumps @ 3000-5299 GPM Per Pump

M2C02

Elevation Section - 6 Pumps @ 3000-5299 GPM Per Pump

M2C03

Base Section - 6 Pumps @ 3000-5299 GPM Per Pump

M2C04

Station Operation Tables - 6 Pumps @ 3000-5299 GPM Per Pump

M2S01

Structural - 6 Pumps @ 3000-5299 GPM Per Pump

M2S02

Structural - 6 Pumps @ 3000-5299 GPM Per Pump

M2S03

Structural - 6 Pumps @ 3000-5299 GPM Per Pump

M2S04

Structural - 6 Pumps @ 3000-5299 GPM Per Pump

Alternate Low Profile Configuration

Drawing No.

Title

M3C01

Plan View @ Grade - 6 Pumps @ 3000-5299 GPM Per Pump

M3C02

Elevation Section - 6 Pumps @ 3000-5299 GPM Per Pump

M3C03

Base Section - 6 Pumps @ 3000-5299 GPM Per Pump

M3C04

Station Operation Tables - 6 Pumps @ 3000-5299 GPM Per Pump

M3S01

Structural - 6 Pumps @ 3000-5299 GPM Per Pump

M3S02

Structural - 6 Pumps @ 3000-5299 GPM Per Pump

M3S03

Structural - 6 Pumps @ 3000-5299 GPM Per Pump

M3S04

Structural - 6 Pumps @ 3000-5299 GPM Per Pump

J SERIES (800-3499 GPM)

Alternate High Profile Configuration

Drawing No.

Title

J1C01

Plan View @ Grade - 4 Pumps @ 800-3499 GPM Per Pump

J1C02

Elevation Section - 4 Pumps @ 800-3499 GPM Per Pump

J1C03

Base Section - 4 Pumps @ 800-3499 GPM Per Pump

J1S01

Structural - 4 Pumps @ 800-3499 GPM Per Pump

J1S02

Structural - 4 Pumps @ 800-3499 GPM Per Pump

J1S03

Structural - 4 Pumps @ 800-3499 GPM Per Pump

Preferred Configuration

Drawing No.

Title

J2C01

Plan View @ Grade - 4 Pumps @ 800-3499 GPM Per Pump

J2C02

Elevation Section - 4 Pumps @ 800-3499 GPM Per Pump

J2C03

Base Section - 4 Pumps @ 800-3499 GPM Per Pump

J2S01

Structural - 4 Pumps @ 800-3499 GPM Per Pump

J2S02

Structural - 4 Pumps @ 800-3499 GPM Per Pump

J2S03

Structural - 4 Pumps @ 800-3499 GPM Per Pump

J2S04

Structural - 4 Pumps @ 800-3499 GPM Per Pump

Alternate Low Profile Configuration

Drawing No.

Title

J3C01

Plan View @ Grade - 4 Pumps @ 800-3499 GPM Per Pump

J3C02

Elevation Section - 4 Pumps @ 800-3499 GPM Per Pump

J3C03

Base Section - 4 Pumps @ 800-3499 GPM Per Pump

J3S01

Structural - 4 Pumps @ 800-3499 GPM Per Pump

J3S02

Structural - 4 Pumps @ 800-3499 GPM Per Pump

J3S03

Structural - 4 Pumps @ 800-3499 GPM Per Pump

J3S04

Structural - 4 Pumps @ 800-3499 GPM Per Pump

K SERIES (2500-3999 GPM)

Alternate High Profile Configuration

Drawing No.

Title

K1C01

Plan View @ Grade - 5 Pumps @ 2500-3999 GPM Per Pump

K1C02

Elevation Section - 5 Pumps @ 2500-3999 GPM Per Pump

K1C03

Base Section - 5 Pumps @ 2500-3999 GPM Per Pump

K1S01

Structural - 5 Pumps @ 2500-3999 GPM Per Pump

K1S02

Structural - 5 Pumps @ 2500-3999 GPM Per Pump

K1S03

Structural - 5 Pumps @ 2500-3999 GPM Per Pump

Preferred Configuration

Drawing No.

Title

K2C01

Plan View @ Grade - 5 Pumps @ 2500-3999 GPM Per Pump

K2C02

Elevation Section - 5 Pumps @ 2500-3999 GPM Per Pump

K2C03

Base Section - 5 Pumps @ 2500-3999 GPM Per Pump

K2C04

Station Operation Tables - 5 Pumps @ 2500-3999 GPM Per Pump

K2S01

Structural - 5 Pumps @ 2500-3999 GPM Per Pump

K2S02

Structural - 5 Pumps @ 2500-3999 GPM Per Pump

K2S03

Structural - 5 Pumps @ 2500-3999 GPM Per Pump

K2S04

Structural - 5 Pumps @ 2500-3999 GPM Per Pump

Alternate Low Profile Configuration

Drawing No.

Title

K3C01

Plan View @ Grade - 5 Pumps @ 2500-3999 GPM Per Pump

K3C02

Elevation Section - 5 Pumps @ 2500-3999 GPM Per Pump

K3C03

Base Section - 5 Pumps @ 2500-3999 GPM Per Pump

K3C04

Station Operation Tables - 5 Pumps @ 2500-3999 GPM Per Pump

K3S01

Structural - 5 Pumps @ 2500-3999 GPM Per Pump

K3S02

Structural - 5 Pumps @ 2500-3999 GPM Per Pump

K3S03

Structural - 5 Pumps @ 2500-3999 GPM Per Pump

K3S04

Structural - 5 Pumps @ 2500-3999 GPM Per Pump

L SERIES ( 3 WET - 2 DRY)

Alternate High Profile Configuration

Drawing No.

Title

L1C01

Plan View @ Grade - 3 Wet & 2 Dry Weather Pumps

L1C02

Elevation Section - 3 Wet & 2 Dry Weather Pumps

L1C03

Base Section - 3 Wet & 2 Dry Weather Pumps

L1S01

Structural - 3 Wet & 2 Dry Weather Pumps

L1S02

Structural - 3 Wet & 2 Dry Weather Pumps

L1S03

Structural - 3 Wet & 2 Dry Weather Pumps

Preferred Configuration

Drawing No.

Title

L2C01

Plan View @ Grade - 3 Wet & 2 Dry Weather Pumps

L2C02

Elevation Section - 3 Wet & 2 Dry Weather Pumps

L2C03

Base Section - 3 Wet & 2 Dry Weather Pumps

L2C04

Station Operation Tables - 3 Wet & 2 Dry Weather Pumps

L2S01

Structural - 3 Wet & 2 Dry Weather Pumps

L2S02

Structural - 3 Wet & 2 Dry Weather Pumps

L2S03

Structural - 3 Wet & 2 Dry Weather Pumps

L2S04

Structural - 3 Wet & 2 Dry Weather Pumps

Alternate Low Profile Configuration

Drawing No.

Title

L3C01

Plan View @ Grade - 3 Wet & 2 Dry Weather Pumps

L3C02

Elevation Section - 3 Wet & 2 Dry Weather Pumps

L3C03

Base Section - 3 Wet & 2 Dry Weather Pumps

L3C04

Station Operation Tables - 3 Wet & 2 Dry Weather Pumps

L3S01

Structural - 3 Wet & 2 Dry Weather Pumps

L3S02

Structural - 3 Wet & 2 Dry Weather Pumps

L3S03

Structural - 3 Wet & 2 Dry Weather Pumps

L3S04

Structural - 3 Wet & 2 Dry Weather Pumps

NOTES TO DESIGN ENGINEER:

A. THESE LIFT STATION DRAWINGS ARE CONSIDERED TO BE DESIGN GUIDELINES FOR THE CONSTRUCTION OF CITY OF HOUSTON WASTEWATER SUBMERSIBLE LIFT STATIONS. THEIR INTENDED USE IS AS A FRAMEWORK FOR THE CONTRACTED DESIGN ENGINEER IN DEVELOPING SPECIFIC LIFT STATION DESIGNS.  
IT IS THE RESPONSIBILITY OF THE CONTRACTED DESIGN ENGINEER TO VERIFY THE COMPLETENESS AND ACCURACY OF THE INFORMATION HEREIN CONTAINED AND TO ADJUST ACCORDING TO SPECIFIC SITE REQUIREMENTS.

B. FOUNDATION REINFORCING SHOWN IS BASED ON SOIL BEARING PRESSURE OF 2000 psf. DESIGN ENGINEER SHALL VERIFY AND ADJUST AS REQUIRED FOR SITE SPECIFIC GEOTECHNICAL RECOMMENDATIONS

C. DESIGN ENGINEER SHALL SELECT THE APPROPRIATE BUILDING LENGTH, MCC CONFIGURATION AND CONTROL PANEL WIDTH (SEE DEVICE RATINGS SCHEDULES ON SHEETS 20E40 THRU 20E44), AND SHALL ADJUST THE FLOOR PLAN (SECTION A1A) AND THE SIDE ELEVATION (VIEW A1D) ACCORDINGLY. SEE SHEET 20E05 FOR ALTERNATE LOCATION OF TRANSFORMER AND LIGHTING PANEL IF REQUIRED, SEE SHEETS 20E40 THRU 20E44.

D. DESIGN ENGINEER SHALL PROVIDE A NORTH ARROW ADJACENT TO THE FLOOR PLAN (SECTION A1A).

E. THE DESIGN ENGINEER SHALL VERIFY THE STRUCTURAL ADEQUACY OF THE BUILDING DESIGN, AND SHALL COMPLETE NOTE NO. 6 PROVIDING THE APPRPRIATE DESIGN CRITERIA USED FOR THIS VERIFICATION.

F. THE DESIGN ENGINEER SHALL DESIGN ROOF TIMBER TRUSSES IN ACCORDANCE WITH SECTION 3 OF THE ENGINEERING DESIGN MANUAL AND THE CITY OF HOUSTON TECHNICAL SPECIFICATIONS SECTION 06193 – PLATE CONNECTED WOOD TRUSSES.

G. THE DESIGN ENGINEER SHALL INCORPORATE ONLY THE NECESSARY STANDARD GUIDELINE DRAWINGS AND DETAILS INTO HIS PROJECT CONTRACT DOCUMENTATION PACKAGE, AND SHALL ADJUST PAGE NUMBERS AND CROSS REFERENCING ACCORDINGLY.

H. THE DESIGN ENGINEER SHALL CONSULT THE CITY OF HOUSTON DESIGN GUIDELINES MANUAL, THE ENGINEERING DESIGN MANUAL, AND THE MASTER SPECIFICATIONS FOR FURTHER INSTRUCTIONS AND INFORMATION PERTINENT TO THESE STANDARD DESIGN GUIDELINE DRAWINGS.

I. THE DESIGN ENGINEER SHALL REMOVE THESE NOTES, ALL REFERENCES TO THESE NOTES, AND ANY OTHER EXTRANEOUS INFORMATION FROM THE DESIGN GUIDELINE DRAWINGS. DESIGN ENGINEER SHALL PROVIDE ANY NOTES OR OTHER APPROPRIATE INFORMATION NECESSARY TO COMPLETE THE LIFT STATION DESIGN.

NOTES:

INDEX

SHEET 2 OF 3

PROJECT NO.

R-0267-02-2

TITLE

CITY OF HOUSTON  
DESIGN GUIDELINE DRAWINGS  
FOR SUBMERSIBLE LIFT STATIONS

CITY OF HOUSTON

DEPARTMENT OF PUBLIC WORKS AND ENGINEERING  
ENGINEERING, CONSTRUCTION AND REAL ESTATE GROUP

APPROVALS

WATER DESIGN

TRAFFIC AND SIGNAL DESIGN

STORM SEWER DESIGN

STREET, BRIDGE & R.O.W.

WASTEWATER DESIGN

CONSTRUCTION

OTHER REVIEWS

PLANNING AND DEVELOPMENT

CITY ENGINEER

DATE

SCALE: AS NOTED

DESIGNED BY:

SUBMITTED:

DRAWN BY:

DATE:

SHEET NO. OF SHEETS

SURVEY BY:

DWG. NO.

FIELD BOOK NO.

INDEX-2

SEAL

CADD DWG. FILE NO. :  
FILENAME.DWG (Scale: ###)

COHSTD.BDR

0123

ORIGINAL SCALE IN INCHES  
FOR REDUCED PLANS

Z SERIES

General

Drawing No.

Title

Z0A01Control Building, Architectural

Z0C01Submersible Transducer Well Level Gauging System & Details

Z0C02Typical Details - Civil

Z0C03Typical Details - Civil

Z0C04Discharge Piping Support Details

Z0C05Typical Catwalk Details

Z0C06Typical Details - Surge Relief Valve Installation

Z0C07Typica Details - Civil

Z0C08Typical Site Details

Z0C09Example - Civil Site Plan

Z0C10Typical Site Details

Z0C11Typical Hatch Details

Z0G01Cover Sheet

Z0S01Structural Standard Details

Z0S02Structural - Standard Details, General Notes and Abbreviations

NOTES TO DESIGN ENGINEER:

A. THESE LIFT STATION DRAWINGS ARE CONSIDERED TO BE DESIGN GUIDELINES FOR THE CONSTRUCTION OF CITY OF HOUSTON WASTEWATER SUBMERSIBLE LIFT STATIONS. THEIR INTENDED USE IS AS A FRAMEWORK FOR THE CONTRACTED DESIGN ENGINEER IN DEVELOPING SPECIFIC LIFT STATION DESIGNS. IT IS THE RESPONSIBILITY OF THE CONTRACTED DESIGN ENGINEER TO VERIFY THE COMPLETENESS AND ACCURACY OF THE INFORMATION HEREIN CONTAINED AND TO ADJUST ACCORDING TO SPECIFIC SITE REQUIREMENTS.

B. FOUNDATION REINFORCING SHOWN IS BASED ON SOIL BEARING PRESSURE OF 2000 psf. DESIGN ENGINEER SHALL VERIFY AND ADJUST AS REQUIRED FOR SITE SPECIFIC GEOTECHNICAL RECOMMENDATIONS.

C. DESIGN ENGINEER SHALL SELECT THE APPROPRIATE BUILDING LENGTH, MCC CONFIGURATION AND CONTROL PANEL WIDTH (SEE DEVICE RATINGS SCHEDULES ON SHEETS Z0E40 THRU Z0E44); AND SHALL ADJUST THE FLOOR PLAN (SECTION A1A) AND THE SIDE ELEVATION (VIEW A1D) ACCORDINGLY. SEE SHEET Z0B05 FOR ALTERNATE LOCATION OF TRANSFORMER AND LIGHTING PANEL IF REQUIRED. SEE SHEETS Z0E40 THRU Z0E44.

D. DESIGN ENGINEER SHALL PROVIDE A NORTH ARROW ADJACENT TO THE FLOOR PLAN (SECTION A1A).

E. THE DESIGN ENGINEER SHALL VERIFY THE STRUCTURAL ADEQUACY OF THE BUILDING DESIGN, AND SHALL COMPLETE NOTE NO. 6 PROVIDING THE APPRPPPIATE DESIGN CRITERIA USED FOR THIS VERIFICATION.

F. THE DESIGN ENGINEER SHALL DESIGN ROOF TIMBER TRUSSES IN ACCORDANCE WITH SECTION 3 OF THE ENGINEERING DESIGN MANUAL AND THE CITY OF HOUSTON TECHNICAL SPECIFICATIONS SECTION 06193 – PLATE CONNECTED WOOD TRUSSES.

G. THE DESIGN ENGINEER SHALL INCORPORATE ONLY THE NECESSARY STANDARD GUIDELINE DRAWINGS AND DETAILS INTO HIS PROJECT CONTRACT DOCUMENTATION PACKAGE, AND SHALL ADJUST PAGE NUMBERS AND CROSS REFERENCING ACCORDINCLY.

H. THE DESIGN ENGINEER SHALL CONSULT THE CITY OF HOUSTON DESIGN GUIDELINES MANUAL, THE ENGINEERING DESIGN MANUAL, AND THE MASTER SPECIFICATIONS FOR FURTHER INSTRUCTIONS AND INFORMATION PERTINENT TO THESE STANDARD DESIGN GUIDELINE DRAWINGS.

I. THE DESIGN ENGINEER SHALL REMOVE THESE NOTES, ALL REFERENCES TO THESE NOTES, AND ANY OTHER EXTRANEIOUS INFORMATION FROM THE DESIGN GUIDELINE DRAWINGS. DESIGN ENGINEER SHALL PROVIDE ANY NOTES OR OTHER APPROPRIATE INFORMATION NECESSARY TO COMPLETE THE LIFT STATION DESIGN.

NOTES:

INDEX

SHEET 3 OF 3

PROJECT NO. R-0267-02-2

TITLECITY OF HOUSTON  
DESIGN GUIDELINE DRAWINGS  
FOR SUBMERSIBLE LIFT STATIONS

CITY OF HOUSTON  
DEPARTMENT OF PUBLIC WORKS AND ENGINEERING  
ENGINEERING, CONSTRUCTION AND REAL ESTATE GROUP

APPROVALS

WATER DESIGN

TRAFFIC AND SIGNAL DESIGN

STORM SEWER DESIGN

STREET, BRIDGE & R.O.W.

WASTEWATER DESIGN

CONSTRUCTION

OTHER REVIEWS

PLANNING AND DEVELOPMENT

CITY ENGINEER

DATE

SCALE:AS NOTED

DESIGNED BY:

SUBMITTED:

DRAWN BY:

DATE:

SHEET NO. OF SHEETS

SURVEY BY:

DWG. NO.

FIELD BOOK NO.

INDEX- 3

SEAL

CADD DWG. FILE NO. :  
FILENAME.DWG (Scale: ###)

COHSTD.BDR

0123

ORIGINAL SCALE IN INCHES  
FOR REDUCED PLANS

REV. NO.

DESCRIPTION

APP'D

DATE

## TITLE & INDEX SHEETS

## 2 Pump Set

### 3 Pump Set

Title Sheet	
File Name & Sheet Numbering	Designation Code
Index Sheet 1	
Index Sheet 2	
Index Sheet 3	
Index Sheet 4	

Drawing No.	Title
Z1E01	ELECTRICAL SYMBOLS LEGENDS, LIGHTING FIXTURE SCHEDULES & ABBREVIATIONS
A1E01	CONDUIT LAYOUT FOR LIFT STATION 2 PUMP ALTERNATE HIGH PROFILE CONFIGURATION
A2E01	CONDUIT LAYOUT FOR LIFT STATION 2 PUMP PREFERRED LOW PROFILE CONFIGURATION
A3E01	CONDUIT LAYOUT FOR LIFT STATION 2 PUMP ALTERNATE LOW PROFILE CONFIGURATION
A3E02	CONDUIT LAYOUT FOR LIFT STATION 2 PUMP ALTERNATE LOW PROFILE CONFIGURATION
B1E01	CONDUIT LAYOUT FOR LIFT STATION 2 PUMP ALTERNATE HIGH PROFILE CONFIGURATION
B2E01	CONDUIT LAYOUT FOR LIFT STATION 2 PUMP PREFERRED LOW PROFILE CONFIGURATION
B3E01	CONDUIT LAYOUT FOR LIFT STATION 2 PUMP ALTERNATE LOW PROFILE CONFIGURATION
B3E02	CONDUIT LAYOUT FOR LIFT STATION 2 PUMP ALTERNATE LOW PROFILE CONFIGURATION
C1E01	CONDUIT LAYOUT FOR LIFT STATION 2 PUMP ALTERNATE HIGH PROFILE CONFIGURATION
C2E01	CONDUIT LAYOUT FOR LIFT STATION 2 PUMP PREFERRED LOW PROFILE CONFIGURATION
C3E01	CONDUIT LAYOUT FOR LIFT STATION 2 PUMP ALTERNATE LOW PROFILE CONFIGURATION
C3E02	CONDUIT LAYOUT FOR LIFT STATION 2 PUMP ALTERNATE LOW PROFILE CONFIGURATION
X0E01	2 PUMP OUTDOOR CONTROL CABINET ENCLOSURE
X0E02	2 PUMP OUTDOOR CONTROL CABINET EQUIPMENT LAYOUT & SCHEDULE
X0E03	2 PUMP OUTDOOR CONTROL CABINET EQUIPMENT LAYOUT
X0E04	2 PUMP OUTDOOR CONTROL CABINET EQUIPMENT LAYOUT
X0E05	2 PUMP OUTDOOR CONTROL CABINET EQUIPMENT LAYOUT
X0E06	2 PUMP OUTDOOR CONTROL PANEL POWER WIRING DIAGRAM
X0E10	2 PUMP OUTDOOR CONTROL PANEL SINGLE LINE DIAGRAM
X0E40	2 PUMP OUTDOOR PROCESS & INSTRUMENTATION DIAGRAM
X0E41	2 PUMP OUTDOOR PROCESS & INSTRUMENTATION DIAGRAM
X0E50	2 PUMP OUTDOOR CONTROL PANEL CONTROL WIRING DIAGRAM
X0E51	2 PUMP OUTDOOR CONTROL PANEL CONTROL WIRING DIAGRAM
X0E52	2 PUMP OUTDOOR CONTROL PANEL CONTROL WIRING DIAGRAM
X0E53	2 PUMP OUTDOOR CONTROL PANEL CONTROL WIRING DIAGRAM
X0E54	2 PUMP OUTDOOR PUMP 101 CONTROL WIRING DIAGRAM
X0E55	2 PUMP OUTDOOR PUMP 102 CONTROL WIRING DIAGRAM
Y0E21	2 PUMP INDOOR CONTROL CABINET EQUIPMENT LAYOUT & SCHEDULE
Y0E22	2 PUMP INDOOR CONTROL CABINET BACK DOOR ELEVATION
Y0E23	2 PUMP INDOOR CONTROL CABINET EQUIPMENT LAYOUT
Y0E25	2 PUMP INDOOR MCC INCOMING POWER SCHEMATIC & CONTROL POWER & COMMUNICATIONS WIRING DIAGRAM
Y0E26	2 PUMP INDOOR MCC POWER SCHEMATIC & CONTROL POWER & COMMUNICATIONS WIRING DIAGRAM
Y0E30	2 PUMP INDOOR SINGLE LINE DIAGRAM
Y0E40	2 PUMP INDOOR PROCESS & INSTRUMENTATION DIAGRAM
Y0E41	2 PUMP INDOOR PROCESS & INSTRUMENTATION DIAGRAM
Y0E50	2 PUMP INDOOR CONTROL PANEL CONTROL WIRING DIAGRAM
Y0E51	2 PUMP INDOOR CONTROL PANEL CONTROL WIRING DIAGRAM
Y0E52	2 PUMP INDOOR CONTROL PANEL CONTROL WIRING DIAGRAM
Y0E58	2 PUMP INDOOR PUMP 101 CONTROL WIRING DIAGRAM
Y0E59	2 PUMP INDOOR PUMP 102 CONTROL WIRING DIAGRAM
Z0C01	SUBMERSIBLE TRANSDUCER WELL LEVEL GAUGING SYSTEM INSTALLATION & DETAILS
Z0E02	2 PUMP (INDOOR/OUTDOOR) TYPICAL JUNCTION BOX DETAILS
Z0E03	2 PUMP (INDOOR/OUTDOOR) TYPICAL ELECTRICAL DETAILS
Z0E04	2 PUMP (INDOOR/OUTDOOR) TYPICAL ELECTRICAL DETAILS
Z0E05	2 PUMP (INDOOR/OUTDOOR) CONTROL BUILDING - ELECTRICAL
Z0E06	- EXAMPLE - ELECTRICAL SITE PLAN ALTERNATE HIGH PROFILE CONFIGURATION
Z0E07	2 PUMP (INDOOR/OUTDOOR) TYPICAL ELECTRICAL DETAILS
Z0E08	2 PUMP (INDOOR/OUTDOOR) TYPICAL ELECTRICAL DETAILS
Z0E15	2 PUMP (INDOOR/OUTDOOR) MCC ELEVATIONS
Z0E21	2 PUMP (INDOOR/OUTDOOR) CONDUIT SCHEDULE FOR 480 VOLT
Z0E45	2 PUMP (INDOOR/OUTDOOR) DEVICE RATING SCHEDULE TYPICAL ELECTRICAL DETAILS

Drawing No.	Title
Z1E01	ELECTRICAL SYMBOLS LEGENDS, LIGHTING FIXTURE SCHEDULES & ABBREVIATIONS
D1E01	CONDUIT LAYOUT FOR LIFT STATION 3 PUMP ALTERNATE HIGH PROFILE CONFIGURATION
D2E01	CONDUIT LAYOUT FOR LIFT STATION 3 PUMP PREFERRED LOW PROFILE CONFIGURATION
D3E01	CONDUIT LAYOUT FOR LIFT STATION 3 PUMP ALTERNATE LOW PROFILE CONFIGURATION
D3E02	CONDUIT LAYOUT FOR LIFT STATION 3 PUMP ALTERNATE LOW PROFILE CONFIGURATION
E1E01	CONDUIT LAYOUT FOR LIFT STATION 3 PUMP ALTERNATE HIGH PROFILE CONFIGURATION
E2E01	CONDUIT LAYOUT FOR LIFT STATION 3 PUMP PREFERRED LOW PROFILE CONFIGURATION
E3E01	CONDUIT LAYOUT FOR LIFT STATION 3 PUMP ALTERNATE LOW PROFILE CONFIGURATION
E3E02	CONDUIT LAYOUT FOR LIFT STATION 3 PUMP ALTERNATE LOW PROFILE CONFIGURATION
F1E01	CONDUIT LAYOUT FOR LIFT STATION 3 PUMP ALTERNATE HIGH PROFILE CONFIGURATION
F2E01	CONDUIT LAYOUT FOR LIFT STATION 3 PUMP PREFERRED LOW PROFILE CONFIGURATION
F3E01	CONDUIT LAYOUT FOR LIFT STATION 3 PUMP ALTERNATE LOW PROFILE CONFIGURATION
F3E02	CONDUIT LAYOUT FOR LIFT STATION 3 PUMP ALTERNATE LOW PROFILE CONFIGURATION
G1E01	CONDUIT LAYOUT FOR LIFT STATION 3 PUMP ALTERNATE HIGH PROFILE CONFIGURATION
G2E01	CONDUIT LAYOUT FOR LIFT STATION 3 PUMP PREFERRED LOW PROFILE CONFIGURATION
G3E01	CONDUIT LAYOUT FOR LIFT STATION 3 PUMP ALTERNATE LOW PROFILE CONFIGURATION
G3E02	CONDUIT LAYOUT FOR LIFT STATION 3 PUMP ALTERNATE LOW PROFILE CONFIGURATION
H1E01	CONDUIT LAYOUT FOR LIFT STATION 3 PUMP ALTERNATE HIGH PROFILE CONFIGURATION
H2E01	CONDUIT LAYOUT FOR LIFT STATION 3 PUMP PREFERRED LOW PROFILE CONFIGURATION
H3E01	CONDUIT LAYOUT FOR LIFT STATION 3 PUMP ALTERNATE LOW PROFILE CONFIGURATION
H3E02	CONDUIT LAYOUT FOR LIFT STATION 3 PUMP ALTERNATE LOW PROFILE CONFIGURATION
X0E01	3 PUMP OUTDOOR CONTROL CABINET ENCLOSURE
X0E02	3 PUMP OUTDOOR CONTROL CABINET EQUIPMENT LAYOUT & SCHEDULE
X0E03	3 PUMP OUTDOOR CONTROL CABINET EQUIPMENT LAYOUT
X0E04	3 PUMP OUTDOOR CONTROL CABINET EQUIPMENT LAYOUT
X0E05	3 PUMP OUTDOOR CONTROL CABINET EQUIPMENT LAYOUT
X0E06	3 PUMP OUTDOOR CONTROL PANEL POWER WIRING DIAGRAM
X0E10	3 PUMP OUTDOOR CONTROL PANEL SINGLE LINE DIAGRAM
X0E40	3 PUMP OUTDOOR PROCESS & INSTRUMENTATION DIAGRAM
X0E41	3 PUMP OUTDOOR PROCESS & INSTRUMENTATION DIAGRAM
X0E50	3 PUMP OUTDOOR CONTROL PANEL CONTROL WIRING DIAGRAM
X0E51	3 PUMP OUTDOOR CONTROL PANEL CONTROL WIRING DIAGRAM
X0E52	3 PUMP OUTDOOR CONTROL PANEL CONTROL WIRING DIAGRAM
X0E53	3 PUMP OUTDOOR CONTROL PANEL CONTROL WIRING DIAGRAM
X0E54	3 PUMP OUTDOOR PUMP 101 CONTROL WIRING DIAGRAM
X0E55	3 PUMP OUTDOOR PUMP 102 CONTROL WIRING DIAGRAM
X0E56	3 PUMP OUTDOOR PUMP 103 CONTROL WIRING DIAGRAM
Y0E21	3 PUMP INDOOR CONTROL CABINET EQUIPMENT LAYOUT & SCHEDULE
Y0E22	3 PUMP INDOOR CONTROL CABINET BACK DOOR ELEVATION
Y0E23	3 PUMP INDOOR CONTROL CABINET EQUIPMENT LAYOUT
Y0E25	3 PUMP INDOOR MCC INCOMING POWER SCHEMATIC & CONTROL POWER & COMMUNICATIONS WIRING DIAGRAM
Y0E26	3 PUMP INDOOR MCC POWER SCHEMATIC & CONTROL POWER & COMMUNICATIONS WIRING DIAGRAM
Y0E30	3 PUMP INDOOR SINGLE LINE DIAGRAM
Y0E31	3 PUMP INDOOR SINGLE LINE DIAGRAM
Y0E40	3 PUMP INDOOR PROCESS & INSTRUMENTATION DIAGRAM
Y0E41	3 PUMP INDOOR PROCESS & INSTRUMENTATION DIAGRAM
Y0E50	3 PUMP INDOOR CONTROL PANEL CONTROL WIRING DIAGRAM
Y0E51	3 PUMP INDOOR CONTROL PANEL CONTROL WIRING DIAGRAM
Y0E52	3 PUMP INDOOR CONTROL PANEL CONTROL WIRING DIAGRAM
Y0E58	3 PUMP INDOOR PUMP 101 CONTROL WIRING DIAGRAM
Y0E59	3 PUMP INDOOR PUMP 102 CONTROL WIRING DIAGRAM
Y0E60	3 PUMP INDOOR PUMP 103 CONTROL WIRING DIAGRAM
Z0C01	SUBMERSIBLE TRANSDUCER WELL LEVEL GAUGING SYSTEM INSTALLATION & DETAILS
Z0E02	3 PUMP (INDOOR/OUTDOOR) TYPICAL JUNCTION BOX DETAILS
Z0E03	3 PUMP (INDOOR/OUTDOOR) TYPICAL ELECTRICAL DETAILS
Z0E04	3 PUMP (INDOOR/OUTDOOR) TYPICAL ELECTRICAL DETAILS
Z0E05	3 PUMP (INDOOR/OUTDOOR) CONTROL BUILDING – ELECTRICAL
Z0E06	– EXAMPLE – ELECTRICAL SITE PLAN ALTERNATE HIGH PROFILE CONFIGURATION
Z0E07	3 PUMP (INDOOR/OUTDOOR) TYPICAL ELECTRICAL DETAILS
Z0E08	3 PUMP (INDOOR/OUTDOOR) TYPICAL ELECTRICAL DETAILS
Z0E13	3 PUMP (INDOOR/OUTDOOR) MCC ELEVATIONS
Z0E21	3 PUMP (INDOOR/OUTDOOR) CONDUIT SCHEDULE FOR 480 VOLT
Z0E42	3 PUMP (INDOOR/OUTDOOR) DEVICE RATING SCHEDULE TYPICAL ELECTRICAL DETAILS

## NOTES TO DESIGN ENGINEER:

- A. THESE LIFT STATION DRAWINGS ARE CONSIDERED TO BE DESIGN GUIDELINES FOR THE CONSTRUCTION OF CITY OF HOUSTON WASTEWATER SUBMERGIBLE LIFT STATIONS. THEIR INTENDED USE IS AS A FRAMEWORK FOR THE CONTRACTED DESIGN ENGINEER IN DEVELOPING SPECIFIC LIFT STATION DESIGNS.  
IT IS THE RESPONSIBILITY OF THE CONTRACTED DESIGN ENGINEER TO VERIFY THE COMPLETENESS AND ACCURACY OF THE INFORMATION HEREIN CONTAINED AND TO ADJUST ACCORDING TO PROJECT SPECIFIC REQUIREMENTS.
- B. POWER FACTOR CORRECTION CAPACITOR IS REQUIRED FOR EACH PUMP RATED AT 20 HP OR GREATER. MOUNT CAPACITORS EXTERNAL TO MCC WITHIN THE CONTROL BUILDING.
- C. UNLESS OTHERWISE INDICATED, ALL DEVICES WITHOUT FURTHER DESIGNATION ARE LOCATED AT THE MOTOR CONTROL CENTER (MCC).
- D. THE DESIGN ENGINEER SHALL INCORPORATE ONLY THE NECESSARY STANDARD GUIDELINE DRAWINGS AND DETAILS INTO HIS PROJECT CONTRACT DOCUMENTATION PACKAGE, AND SHALL ADJUST PACE NUMBERS AND CROSS REFERENCING ACCORDINGLY.
- E. THE DESIGN ENGINEER SHALL CONSULT THE CITY OF HOUSTON DESIGN GUIDELINES MANUAL, THE ENGINEERING DESIGN MANUAL, AND THE MASTER SPECIFICATIONS FOR FURTHER INSTRUCTIONS AND INFORMATION PERTINENT TO THESE STANDARD DESIGN GUIDELINE DRAWINGS.
- F. THE DESIGN ENGINEER SHALL REMOVE THESE NOTES, ALL REFERENCES TO THESE NOTES, AND ANY OTHER EXTRANEOUS INFORMATION FROM THE DESIGN GUIDELINE DRAWING. THE DESIGN ENGINEER SHALL PROVIDE ANY NOTES OR OTHER APPROPRIATE INFORMATION NECESSARY TO COMPLETE THE LIFT STATION DESIGN.

NOTES:

<b>INDEX</b> <b>SHEET 1 OF 4</b>	
PROJECT NO. <span style="float: right;">R-000265-0XXX-X</span>	
TITLE <span style="float: right;">CITY OF HOUSTON DESIGN GUIDELINE DRAWINGS FOR SUBMERSIBLE LIFT STATIONS</span>	
<b>CITY OF HOUSTON</b> DEPARTMENT OF PUBLIC WORKS AND ENGINEERING ENGINEERING AND CONSTRUCTION	
<b>APPROVALS</b>	
WATER DESIGN	TRAFFIC AND SIGNAL DESIGN
STORM SEWER DESIGN	STREET, BRIDGE & R.O.W.
WASTEWATER DESIGN	CONSTRUCTION
<b>OTHER REVIEWS</b>	
PLANNING AND DEVELOPMENT	
CITY ENGINEER	DATE
SCALE: <span style="float: right;">AS NOTED</span>	DESIGNED BY:
SUBMITTED:	DRAWN BY:
DATE:	SHEET NO.      OF      SHEETS
SURVEY BY:	DWG. NO.
FIELD BOOK NO.	<b>INDEX-1</b>



3W2D Pump Set

Drawing No. Title

Z1E01ELECTRICAL SYMBOLS LEGENDS, LIGHTING FIXTURE SCHEDULES & ABBREVIATIONS

L1E01CONDUIT LAYOUT FOR LIFT STATION 3 WET & 2 DRY WEATHER PUMPS ALTERNATE HIGH PROFILE CONFIGURATION

L2E01CONDUIT LAYOUT FOR LIFT STATION 3 WET & 2 DRY WEATHER PUMPS PREFERRED LOW PROFILE CONFIGURATION

L3E01CONDUIT LAYOUT FOR LIFT STATION 3 WET & 2 DRY WEATHER PUMPS ALTERNATE LOW PROFILE CONFIGURATION

L3E02CONDUIT LAYOUT FOR LIFT STATION 3 WET & 2 DRY WEATHER PUMPS ALTERNATE LOW PROFILE CONFIGURATION

Y0E213 WET & 2 DRY WEATHER PUMPS INDOOR CONTROL CABINET EQUIPMENT LAYOUT & SCHEDULE

Y0E223 WET & 2 DRY WEATHER PUMPS INDOOR CONTROL CABINET BACK DOOR ELEVATION

Y0E233 WET & 2 DRY WEATHER PUMPS INDOOR CONTROL CABINET EQUIPMENT LAYOUT

Y0E253 WET & 2 DRY WEATHER PUMPS INDOOR MCC INCOMING POWER SCHEMATIC & CONTROL POWER & COMMUNICATIONS WIRING DIAGRAM

Y0E263 WET & 2 DRY WEATHER PUMPS INDOOR MCC POWER SCHEMATIC & CONTROL POWER & COMMUNICATIONS WIRING DIAGRAM

Y0E303 WET & 2 DRY WEATHER PUMPS INDOOR SINGLE LINE DIAGRAM

Y0E313 WET & 2 DRY WEATHER PUMPS INDOOR SINGLE LINE DIAGRAM

Y0E403 WET & 2 DRY WEATHER PUMPS INDOOR PROCESS & INSTRUMENTATION DIAGRAM

Y0E413 WET & 2 DRY WEATHER PUMPS INDOOR PROCESS & INSTRUMENTATION DIAGRAM

Y0E503 WET & 2 DRY WEATHER PUMPS INDOOR CONTROL PANEL CONTROL WIRING DIAGRAM

Y0E513 WET & 2 DRY WEATHER PUMPS INDOOR CONTROL PANEL CONTROL WIRING DIAGRAM

Y0E523 WET & 2 DRY WEATHER PUMPS INDOOR CONTROL PANEL CONTROL WIRING DIAGRAM

Y0E583 WET & 2 DRY WEATHER PUMPS INDOOR PUMP W101 CONTROL WIRING DIAGRAM

Y0E593 WET & 2 DRY WEATHER PUMPS INDOOR PUMP W102 CONTROL WIRING DIAGRAM

Y0E603 WET & 2 DRY WEATHER PUMPS INDOOR PUMP D103 CONTROL WIRING DIAGRAM

Y0E613 WET & 2 DRY WEATHER PUMPS INDOOR PUMP D104 CONTROL WIRING DIAGRAM

Y0E623 WET & 2 DRY WEATHER PUMPS INDOOR PUMP D105 CONTROL WIRING DIAGRAM

Z0C01SUBMERSIBLE TRANSDUCER WELL LEVEL GAUGING SYSTEM INSTALLATION & DETAILS

Z0E023 WET & 2 DRY WEATHER PUMPS TYPICAL JUNCTION BOX DETAILS

Z0E033 WET & 2 DRY WEATHER PUMPS TYPICAL ELECTRICAL DETAILS

Z0E043 WET & 2 DRY WEATHER PUMPS TYPICAL ELECTRICAL DETAILS

Z0E053 WET & 2 DRY WEATHER PUMPS CONTROL BUILDING – ELECTRICAL

Z0E06– EXAMPLE – ELECTRICAL SITE PLAN ALTERNATE HIGH PROFILE CONFIGURATION

Z0E073 WET & 2 DRY WEATHER PUMPS TYPICAL ELECTRICAL DETAILS

Z0E083 WET & 2 DRY WEATHER PUMPS TYPICAL ELECTRICAL DETAILS

Z0E133 WET & 2 DRY WEATHER PUMPS MCC ELEVATIONS

Z0E213 WET & 2 DRY WEATHER PUMPS CONDUIT SCHEDULE FOR 480 VOLT

Z0E223 WET & 2 DRY WEATHER PUMPS CONDUIT SCHEDULE FOR 480 VOLT

Z0E423 WET & 2 DRY WEATHER PUMPS DEVICE RATING SCHEDULE TYPICAL ELECTRICAL DETAILS

Z0E433 WET & 2 DRY WEATHER PUMPS DEVICE RATING SCHEDULE TYPICAL ELECTRICAL DETAILS

4 Pump Set

Drawing No. Title

Z1E01ELECTRICAL SYMBOLS LEGENDS, LIGHTING FIXTURE SCHEDULES & ABBREVIATIONS

I1E01CONDUIT LAYOUT FOR LIFT STATION 4 PUMP ALTERNATE HIGH PROFILE CONFIGURATION

I2E01CONDUIT LAYOUT FOR LIFT STATION 4 PUMP PREFERRED LOW PROFILE CONFIGURATION

I3E01CONDUIT LAYOUT FOR LIFT STATION 4 PUMP ALTERNATE LOW PROFILE CONFIGURATION

I3E02CONDUIT LAYOUT FOR LIFT STATION 4 PUMP ALTERNATE LOW PROFILE CONFIGURATION

J1E01CONDUIT LAYOUT FOR LIFT STATION 4 PUMP ALTERNATE HIGH PROFILE CONFIGURATION

J2E01CONDUIT LAYOUT FOR LIFT STATION 4 PUMP PREFERRED LOW PROFILE CONFIGURATION

J3E01CONDUIT LAYOUT FOR LIFT STATION 4 PUMP ALTERNATE LOW PROFILE CONFIGURATION

J3E02CONDUIT LAYOUT FOR LIFT STATION 4 PUMP ALTERNATE LOW PROFILE CONFIGURATION

X0E014 PUMP OUTDOOR CONTROL CABINET ENCLOSURE

X0E024 PUMP OUTDOOR CONTROL CABINET EQUIPMENT LAYOUT & SCHEDULE

X0E034 PUMP OUTDOOR CONTROL CABINET EQUIPMENT LAYOUT

X0E044 PUMP OUTDOOR CONTROL CABINET EQUIPMENT LAYOUT

X0E054 PUMP OUTDOOR CONTROL CABINET EQUIPMENT LAYOUT

X0E064 PUMP OUTDOOR CONTROL PANEL POWER WIRING DIAGRAM

X0E104 PUMP OUTDOOR CONTROL PANEL SINGLE LINE DIAGRAM

X0E404 PUMP OUTDOOR PROCESS & INSTRUMENTATION DIAGRAM

X0E414 PUMP OUTDOOR PROCESS & INSTRUMENTATION DIAGRAM

X0E504 PUMP OUTDOOR CONTROL PANEL CONTROL WIRING DIAGRAM

X0E514 PUMP OUTDOOR CONTROL PANEL CONTROL WIRING DIAGRAM

X0E524 PUMP OUTDOOR CONTROL PANEL CONTROL WIRING DIAGRAM

X0E534 PUMP OUTDOOR CONTROL PANEL CONTROL WIRING DIAGRAM

X0E544 PUMP OUTDOOR PUMP 101 CONTROL WIRING DIAGRAM

X0E554 PUMP OUTDOOR PUMP 102 CONTROL WIRING DIAGRAM

X0E564 PUMP OUTDOOR PUMP 103 CONTROL WIRING DIAGRAM

X0E574 PUMP OUTDOOR PUMP 104 CONTROL WIRING DIAGRAM

Y0E214 PUMP INDOOR CONTROL CABINET EQUIPMENT LAYOUT & SCHEDULE

Y0E224 PUMP INDOOR CONTROL CABINET BACK DOOR ELEVATION

Y0E234 PUMP INDOOR CONTROL CABINET EQUIPMENT LAYOUT

Y0E254 PUMP INDOOR MCC INCOMING POWER SCHEMATIC & CONTROL POWER & COMMUNICATIONS WIRING DIAGRAM

Y0E264 PUMP INDOOR MCC POWER SCHEMATIC & CONTROL POWER & COMMUNICATIONS WIRING DIAGRAM

Y0E304 PUMP INDOOR SINGLE LINE DIAGRAM

Y0E314 PUMP INDOOR SINGLE LINE DIAGRAM

Y0E404 PUMP INDOOR PROCESS & INSTRUMENTATION DIAGRAM

Y0E414 PUMP INDOOR PROCESS & INSTRUMENTATION DIAGRAM

Y0E504 PUMP INDOOR CONTROL PANEL CONTROL WIRING DIAGRAM

Y0E514 PUMP INDOOR CONTROL PANEL CONTROL WIRING DIAGRAM

Y0E524 PUMP INDOOR CONTROL PANEL CONTROL WIRING DIAGRAM

Y0E584 PUMP INDOOR PUMP 101 CONTROL WIRING DIAGRAM

Y0E594 PUMP INDOOR PUMP 102 CONTROL WIRING DIAGRAM

Y0E604 PUMP INDOOR PUMP 103 CONTROL WIRING DIAGRAM

Y0E614 PUMP INDOOR PUMP 104 CONTROL WIRING DIAGRAM

Z0C01SUBMERSIBLE TRANSDUCER WELL LEVEL GAUGING SYSTEM INSTALLATION & DETAILS

Z0E024 PUMP (INDOOR/OUTDOOR) TYPICAL JUNCTION BOX DETAILS

Z0E034 PUMP (INDOOR/OUTDOOR) TYPICAL ELECTRICAL DETAILS

Z0E044 PUMP (INDOOR/OUTDOOR) TYPICAL ELECTRICAL DETAILS

Z0E054 PUMP (INDOOR/OUTDOOR) CONTROL BUILDING – ELECTRICAL

Z0E06– EXAMPLE – ELECTRICAL SITE PLAN ALTERNATE HIGH PROFILE CONFIGURATION

Z0E074 PUMP (INDOOR/OUTDOOR) TYPICAL ELECTRICAL DETAILS

Z0E084 PUMP (INDOOR/OUTDOOR) TYPICAL ELECTRICAL DETAILS

Z0E134 PUMP (INDOOR/OUTDOOR) MCC ELEVATIONS

Z0E214 PUMP (INDOOR/OUTDOOR) CONDUIT SCHEDULE FOR 480 VOLT

Z0E424 PUMP (INDOOR/OUTDOOR) DEVICE RATING SCHEDULE TYPICAL ELECTRICAL DETAILS

INDEX

SHEET 2 OF 4

PROJECT NO.

R-000265-0XXX-X

TITLE

CITY OF HOUSTON  
DESIGN GUIDELINE DRAWINGS  
FOR SUBMERSIBLE LIFT STATIONS

CITY OF HOUSTON

DEPARTMENT OF PUBLIC WORKS AND ENGINEERING  
ENGINEERING AND CONSTRUCTION

APPROVALS

WATER DESIGN

TRAFFIC AND SIGNAL DESIGN

STORM SEWER DESIGN

STREET, BRIDGE & R.O.W.

WASTEWATER DESIGN

CONSTRUCTION

OTHER REVIEWS

PLANNING AND DEVELOPEMENT

CITY ENGINEER

DATE

SCALE:AS NOTED

DESIGNED BY:

SUBMITTED:

DRAWN BY:

DATE:

SHEET NO. OF SHEETS

SURVEY BY:

DWG. NO.

FIELD BOOK NO.

INDEX-2

CADD DWG. FILE NO. :  
INDEX SHEET 2 OF 4.DWG

COHSTD.BDR

0123

ORIGINAL SCALE IN INCHES  
FOR REDUCED PLANS

REV. NO.

DESCRIPTION

APP'D

DATE

4W2D Pump Set

Drawing No. Title

Z1E01ELECTRICAL SYMBOLS LEGENDS, LIGHTING FIXTURE SCHEDULES & ABBREVIATIONS

N1E01CONDUIT LAYOUT FOR LIFT STATION 4 WET & 2 DRY WEATHER PUMPS ALTERNATE HIGH PROFILE CONFIGURATION

N2E01CONDUIT LAYOUT FOR LIFT STATION 4 WET & 2 DRY WEATHER PUMPS PREFERRED LOW PROFILE CONFIGURATION

N2E02CONDUIT LAYOUT FOR LIFT STATION 4 WET & 2 DRY WEATHER PUMPS PREFERRED CONFIGURATION

N3E01CONDUIT LAYOUT FOR LIFT STATION 4 WET & 2 DRY WEATHER PUMPS ALTERNATE LOW PROFILE CONFIGURATION

N3E02CONDUIT LAYOUT FOR LIFT STATION 4 WET & 2 DRY WEATHER PUMPS ALTERNATE LOW PROFILE CONFIGURATION

Y0E214 WET & 2 DRY WEATHER PUMPS INDOOR CONTROL CABINET EQUIPMENT LAYOUT & SCHEDULE

Y0E224 WET & 2 DRY WEATHER PUMPS INDOOR CONTROL CABINET BACK DOOR ELEVATION

Y0E234 WET & 2 DRY WEATHER PUMPS INDOOR CONTROL CABINET EQUIPMENT LAYOUT

Y0E254 WET & 2 DRY WEATHER PUMPS INDOOR MCC INCOMING POWER SCHEMATIC & CONTROL POWER & COMMUNICATIONS WIRING DIAGRAM

Y0E264 WET & 2 DRY WEATHER PUMPS INDOOR MCC POWER SCHEMATIC & CONTROL POWER & COMMUNICATIONS WIRING DIAGRAM

Y0E314 WET & 2 DRY WEATHER PUMPS INDOOR SINGLE LINE DIAGRAM

Y0E404 WET & 2 DRY WEATHER PUMPS INDOOR PROCESS & INSTRUMENTATION DIAGRAM

Y0E414 WET & 2 DRY WEATHER PUMPS INDOOR PROCESS & INSTRUMENTATION DIAGRAM

Y0E504 WET & 2 DRY WEATHER PUMPS INDOOR CONTROL PANEL CONTROL WIRING DIAGRAM

Y0E514 WET & 2 DRY WEATHER PUMPS INDOOR CONTROL PANEL CONTROL WIRING DIAGRAM

Y0E524 WET & 2 DRY WEATHER PUMPS INDOOR CONTROL PANEL CONTROL WIRING DIAGRAM

Y0E534 WET & 2 DRY WEATHER PUMPS INDOOR CONTROL PANEL CONTROL WIRING DIAGRAM

Y0E584 WET & 2 DRY WEATHER PUMPS INDOOR PUMP W101 CONTROL WIRING DIAGRAM

Y0E594 WET & 2 DRY WEATHER PUMPS INDOOR PUMP W102 CONTROL WIRING DIAGRAM

Y0E604 WET & 2 DRY WEATHER PUMPS INDOOR PUMP W103 CONTROL WIRING DIAGRAM

Y0E614 WET & 2 DRY WEATHER PUMPS INDOOR PUMP W104 CONTROL WIRING DIAGRAM

Y0E624 WET & 2 DRY WEATHER PUMPS INDOOR PUMP D105 CONTROL WIRING DIAGRAM

Y0E634 WET & 2 DRY WEATHER PUMPS INDOOR PUMP D106 CONTROL WIRING DIAGRAM

Z0C01SUBMERSIBLE TRANSDUCER WELL LEVEL GAUGING SYSTEM INSTALLATION & DETAILS

Z0E024 WET & 2 DRY WEATHER PUMPS TYPICAL JUNCTION BOX DETAILS

Z0E034 WET & 2 DRY WEATHER PUMPS TYPICAL ELECTRICAL DETAILS

Z0E044 WET & 2 DRY WEATHER PUMPS TYPICAL ELECTRICAL DETAILS

Z0E054 WET & 2 DRY WEATHER PUMPS CONTROL BUILDING – ELECTRICAL

Z0E06– EXAMPLE – ELECTRICAL SITE PLAN ALTERNATE HIGH PROFILE CONFIGURATION

Z0E074 WET & 2 DRY WEATHER PUMPS TYPICAL ELECTRICAL DETAILS

Z0E084 WET & 2 DRY WEATHER PUMPS TYPICAL ELECTRICAL DETAILS

Z0E134 WET & 2 DRY WEATHER PUMPS MCC ELEVATIONS

Z0E214 WET & 2 DRY WEATHER PUMPS CONDUIT SCHEDULE FOR 480 VOLT

Z0E224 WET & 2 DRY WEATHER PUMPS CONDUIT SCHEDULE FOR 480 VOLT

Z0E454 WET & 2 DRY WEATHER PUMPS DEVICE RATING SCHEDULE TYPICAL ELECTRICAL DETAILS

Z0E464 WET & 2 DRY WEATHER PUMPS DEVICE RATING SCHEDULE TYPICAL ELECTRICAL DETAILS

Z0E474 WET & 2 DRY WEATHER PUMPS DEVICE RATING SCHEDULE TYPICAL ELECTRICAL DETAILS

5 Pump Set

Drawing No. Title

Z1E01ELECTRICAL SYMBOLS LEGENDS, LIGHTING FIXTURE SCHEDULES & ABBREVIATIONS

K1E01CONDUIT LAYOUT FOR LIFT STATION 5 PUMP ALTERNATE HIGH PROFILE CONFIGURATION

K2E01CONDUIT LAYOUT FOR LIFT STATION 5 PUMP PREFERRED LOW PROFILE CONFIGURATION

K3E01CONDUIT LAYOUT FOR LIFT STATION 5 PUMP ALTERNATE LOW PROFILE CONFIGURATION

K3E02CONDUIT LAYOUT FOR LIFT STATION 5 PUMP ALTERNATE LOW PROFILE CONFIGURATION

Y0E215 PUMP INDOOR CONTROL CABINET EQUIPMENT LAYOUT & SCHEDULE

Y0E225 PUMP INDOOR CONTROL CABINET BACK DOOR ELEVATION

Y0E235 PUMP INDOOR CONTROL CABINET EQUIPMENT LAYOUT

Y0E255 PUMP INDOOR MCC INCOMING POWER SCHEMATIC & CONTROL POWER & COMMUNICATIONS WIRING DIAGRAM

Y0E265 PUMP INDOOR MCC POWER SCHEMATIC & CONTROL POWER & COMMUNICATIONS WIRING DIAGRAM

Y0E305 PUMP INDOOR SINGLE LINE DIAGRAM

Y0E315 PUMP INDOOR SINGLE LINE DIAGRAM

Y0E405 PUMP INDOOR PROCESS & INSTRUMENTATION DIAGRAM

Y0E415 PUMP INDOOR PROCESS & INSTRUMENTATION DIAGRAM

Y0E505 PUMP INDOOR CONTROL PANEL CONTROL WIRING DIAGRAM

Y0E515 PUMP INDOOR CONTROL PANEL CONTROL WIRING DIAGRAM

Y0E525 PUMP INDOOR CONTROL PANEL CONTROL WIRING DIAGRAM

Y0E585 PUMP INDOOR PUMP 101 CONTROL WIRING DIAGRAM

Y0E595 PUMP INDOOR PUMP 102 CONTROL WIRING DIAGRAM

Y0E605 PUMP INDOOR PUMP 103 CONTROL WIRING DIAGRAM

Y0E615 PUMP INDOOR PUMP 104 CONTROL WIRING DIAGRAM

Y0E625 PUMP INDOOR PUMP 105 CONTROL WIRING DIAGRAM

Z0C01SUBMERSIBLE TRANSDUCER WELL LEVEL GAUGING SYSTEM INSTALLATION & DETAILS

Z0E025 PUMP INDOOR TYPICAL JUNCTION BOX DETAILS

Z0E035 PUMP INDOOR TYPICAL ELECTRICAL DETAILS

Z0E045 PUMP INDOOR TYPICAL ELECTRICAL DETAILS

Z0E055 PUMP INDOOR CONTROL BUILDING – ELECTRICAL

Z0E06– EXAMPLE – ELECTRICAL SITE PLAN ALTERNATE HIGH PROFILE CONFIGURATION

Z0E075 PUMP INDOOR TYPICAL ELECTRICAL DETAILS

Z0E085 PUMP INDOOR TYPICAL ELECTRICAL DETAILS

Z0E135 PUMP INDOOR MCC ELEVATIONS

Z0E215 PUMP INDOOR CONDUIT SCHEDULE FOR 480 VOLT

Z0E225 PUMP INDOOR CONDUIT SCHEDULE FOR 480 VOLT

Z0E425 PUMP INDOOR DEVICE RATING SCHEDULE TYPICAL ELECTRICAL DETAILS

INDEX

SHEET 3 OF 4

PROJECT NO.

R-000265-0XXX-X

TITLE

CITY OF HOUSTON  
DESIGN GUIDELINE DRAWINGS  
FOR SUBMERSIBLE LIFT STATIONS

CITY OF HOUSTON

DEPARTMENT OF PUBLIC WORKS AND ENGINEERING  
ENGINEERING AND CONSTRUCTION

APPROVALS

WATER DESIGN

TRAFFIC AND SIGNAL DESIGN

STORM SEWER DESIGN

STREET, BRIDGE & R.O.W.

WASTEWATER DESIGN

CONSTRUCTION

OTHER REVIEWS

PLANNING AND DEVELOPEMENT

CITY ENGINEER

DATE

SCALE:AS NOTED

DESIGNED BY:

SUBMITTED:

DRAWN BY:

DATE:

SHEET NO. OF SHEETS

SURVEY BY:

DWG. NO.

FIELD BOOK NO.

INDEX-3

CADD DWG. FILE NO. :  
INDEX SHEET 3 OF 4.DWG

COHSTD.BDR

0

1

2

3

ORIGINAL SCALE IN INCHES  
FOR REDUCED PLANS

REV. NO.

DESCRIPTION

APP'D

DATE

6 Pump Set

6 VFD Pump Set

Drawing No. Title

Z1E01	ELECTRICAL SYMBOLS LEGENDS, LIGHTING FIXTURE SCHEDULES & ABBREVIATIONS
M1E01	CONDUIT LAYOUT FOR LIFT STATION 6 PUMP ALTERNATE HIGH PROFILE CONFIGURATION
M2E01	CONDUIT LAYOUT FOR LIFT STATION 6 PUMP PREFERRED LOW PROFILE CONFIGURATION
M3E01	CONDUIT LAYOUT FOR LIFT STATION 6 PUMP ALTERNATE LOW PROFILE CONFIGURATION
M3E02	CONDUIT LAYOUT FOR LIFT STATION 6 PUMP ALTERNATE LOW PROFILE CONFIGURATION
Y0E21	6 PUMP INDOOR CONTROL CABINET EQUIPMENT LAYOUT & SCHEDULE
Y0E22	6 PUMP INDOOR CONTROL CABINET BACK DOOR ELEVATION
Y0E23	6 PUMP INDOOR CONTROL CABINET EQUIPMENT LAYOUT
Y0E25	6 PUMP INDOOR MCC INCOMING POWER SCHEMATIC & CONTROL POWER & COMMUNICATIONS WIRING DIAGRAM
Y0E26	6 PUMP INDOOR MCC POWER SCHEMATIC & CONTROL POWER & COMMUNICATIONS WIRING DIAGRAM
Y0E31	6 PUMP INDOOR SINGLE LINE DIAGRAM
Y0E40	6 PUMP INDOOR PROCESS & INSTRUMENTATION DIAGRAM
Y0E41	6 PUMP INDOOR PROCESS & INSTRUMENTATION DIAGRAM
Y0E50	6 PUMP INDOOR CONTROL PANEL CONTROL WIRING DIAGRAM
Y0E51	6 PUMP INDOOR CONTROL PANEL CONTROL WIRING DIAGRAM
Y0E52	6 PUMP INDOOR CONTROL PANEL CONTROL WIRING DIAGRAM
Y0E58	6 PUMP INDOOR PUMP 101 CONTROL WIRING DIAGRAM
Y0E59	6 PUMP INDOOR PUMP 102 CONTROL WIRING DIAGRAM
Y0E60	6 PUMP INDOOR PUMP 103 CONTROL WIRING DIAGRAM
Y0E61	6 PUMP INDOOR PUMP 104 CONTROL WIRING DIAGRAM
Y0E62	6 PUMP INDOOR PUMP 105 CONTROL WIRING DIAGRAM
Y0E63	6 PUMP INDOOR PUMP 106 CONTROL WIRING DIAGRAM
Z0C01	SUBMERSIBLE TRANSDUCER WELL LEVEL GAUGING SYSTEM INSTALLATION & DETAILS
Z0E02	6 PUMP TYPICAL JUNCTION BOX DETAILS
Z0E03	6 PUMP TYPICAL ELECTRICAL DETAILS
Z0E04	6 PUMP TYPICAL ELECTRICAL DETAILS
Z0E05	6 PUMP CONTROL BUILDING – ELECTRICAL
Z0E06	– EXAMPLE – ELECTRICAL SITE PLAN ALTERNATE HIGH PROFILE CONFIGURATION
Z0E07	6 PUMP TYPICAL ELECTRICAL DETAILS
Z0E08	6 PUMP TYPICAL ELECTRICAL DETAILS
Z0E13	6 PUMP MCC ELEVATIONS
Z0E21	6 PUMP CONDUIT SCHEDULE FOR 480 VOLT
Z0E22	6 PUMP CONDUIT SCHEDULE FOR 480 VOLT
Z0E42	6 PUMP DEVICE RATING SCHEDULE TYPICAL ELECTRICAL DETAILS

Drawing No. Title

Z1E01	ELECTRICAL SYMBOLS LEGENDS, LIGHTING FIXTURE SCHEDULES & ABBREVIATIONS
01E01	CONDUIT LAYOUT FOR LIFT STATION 6 PUMP VFD ALTERNATE HIGH PROFILE CONFIGURATION
02E01	CONDUIT LAYOUT FOR LIFT STATION 6 PUMP VFD PREFERRED LOW PROFILE CONFIGURATION
03E01	CONDUIT LAYOUT FOR LIFT STATION 6 PUMP VFD ALTERNATE LOW PROFILE CONFIGURATION
03E02	CONDUIT LAYOUT FOR LIFT STATION 6 PUMP VFD ALTERNATE LOW PROFILE CONFIGURATION
Y0E21	6 PUMP VFD INDOOR CONTROL CABINET EQUIPMENT LAYOUT & SCHEDULE
Y0E22	6 PUMP VFD INDOOR CONTROL CABINET BACK DOOR ELEVATION
Y0E23	6 PUMP VFD INDOOR CONTROL CABINET EQUIPMENT LAYOUT
Y0E25	6 PUMP VFD INDOOR MCC INCOMING POWER SCHEMATIC & CONTROL POWER & COMMUNICATIONS WIRING DIAGRAM
Y0E26	6 PUMP VFD INDOOR MCC POWER SCHEMATIC & CONTROL POWER & COMMUNICATIONS WIRING DIAGRAM
Y0E31	6 PUMP VFD INDOOR SINGLE LINE DIAGRAM
Y0E32	6 PUMP VFD INDOOR SINGLE LINE DIAGRAM
Y0E40	6 PUMP VFD INDOOR PROCESS & INSTRUMENTATION DIAGRAM
Y0E41	6 PUMP VFD INDOOR PROCESS & INSTRUMENTATION DIAGRAM
Y0E50	6 PUMP VFD INDOOR CONTROL PANEL CONTROL WIRING DIAGRAM
Y0E51	6 PUMP VFD INDOOR CONTROL PANEL CONTROL WIRING DIAGRAM
Y0E52	6 PUMP VFD INDOOR CONTROL PANEL CONTROL WIRING DIAGRAM
Y0E58	6 PUMP VFD INDOOR PUMP 101 CONTROL WIRING DIAGRAM
Y0E59	6 PUMP VFD INDOOR PUMP 102 CONTROL WIRING DIAGRAM
Y0E60	6 PUMP VFD INDOOR PUMP 103 CONTROL WIRING DIAGRAM
Y0E61	6 PUMP VFD INDOOR PUMP 104 CONTROL WIRING DIAGRAM
Y0E62	6 PUMP VFD INDOOR PUMP 105 CONTROL WIRING DIAGRAM
Y0E63	6 PUMP VFD INDOOR PUMP 106 CONTROL WIRING DIAGRAM
Z0C01	SUBMERSIBLE TRANSDUCER WELL LEVEL GAUGING SYSTEM INSTALLATION & DETAILS
Z0E02	6 PUMP VFD INDOOR TYPICAL JUNCTION BOX DETAILS
Z0E03	6 PUMP VFD INDOOR TYPICAL ELECTRICAL DETAILS
Z0E04	6 PUMP VFD INDOOR TYPICAL ELECTRICAL DETAILS
Z0E05	6 PUMP VFD INDOOR CONTROL BUILDING – ELECTRICAL
Z0E06	– EXAMPLE – ELECTRICAL SITE PLAN ALTERNATE HIGH PROFILE CONFIGURATION
Z0E07	6 PUMP VFD INDOOR TYPICAL ELECTRICAL DETAILS
Z0E08	6 PUMP VFD INDOOR TYPICAL ELECTRICAL DETAILS
Z0E13	6 PUMP VFD INDOOR MCC ELEVATIONS
Z0E14	6 PUMP VFD INDOOR MCC ELEVATIONS
Z0E15	6 PUMP VFD INDOOR MCC ELEVATIONS
Z0E21	6 PUMP VFD INDOOR CONDUIT SCHEDULE FOR 480 VOLT
Z0E22	6 PUMP VFD INDOOR CONDUIT SCHEDULE FOR 480 VOLT
Z0E42	6 PUMP VFD INDOOR DEVICE RATING SCHEDULE TYPICAL ELECTRICAL DETAILS

NOTES TO DESIGN ENGINEER:

- A. THESE LIFT STATION DRAWINGS ARE CONSIDERED TO BE DESIGN GUIDELINES FOR THE CONSTRUCTION OF CITY OF HOUSTON WASTEWATER SUBMERSIBLE LIFT STATIONS. THEIR INTENDED USE IS AS A FRAMEWORK FOR THE CONTRACTED DESIGN ENGINEER IN DEVELOPING SPECIFIC LIFT STATION DESIGNS.
- IT IS THE RESPONSIBILITY OF THE CONTRACTED DESIGN ENGINEER TO VERIFY THE COMPLETENESS AND ACCURACY OF THE INFORMATION HEREIN CONTAINED AND TO ADJUST ACCORDING TO PROJECT SPECIFIC REQUIREMENTS.
- B. POWER FACTOR CORRECTION CAPACITOR IS REQUIRED FOR EACH PUMP RATED AT 20 HP OR GREATER. MOUNT CAPACITORS EXTERNAL TO MCC WITHIN THE CONTROL BUILDING.
- C. UNLESS OTHERWISE INDICATED, ALL DEVICES WITHOUT FURTHER DESIGNATION ARE LOCATED AT THE MOTOR CONTROL CENTER (MCC).
- D. THE DESIGN ENGINEER SHALL INCORPORATE ONLY THE NECESSARY STANDARD GUIDELINE DRAWINGS AND DETAILS INTO HIS PROJECT CONTRACT DOCUMENTATION PACKAGE, AND SHALL ADJUST PAGE NUMBERS AND CROSS REFERENCING ACCORDINGLY.
- E. THE DESIGN ENGINEER SHALL CONSULT THE CITY OF HOUSTON DESIGN GUIDELINES MANUAL, THE ENGINEERING DESIGN MANUAL, AND THE MASTER SPECIFICATIONS FOR FURTHER INSTRUCTIONS AND INFORMATION PERTINENT TO THESE STANDARD DESIGN GUIDELINE DRAWINGS.
- F. THE DESIGN ENGINEER SHALL REMOVE THESE NOTES, ALL REFERENCES TO THESE NOTES, AND ANY OTHER EXTRANEIOUS INFORMATION FROM THE DESIGN GUIDELINE DRAWINGS. DESIGN ENGINEER SHALL PROVIDE ANY NOTES OR OTHER APPROPRIATE INFORMATION NECESSARY TO COMPLETE THE LIFT STATION DESIGN.

NOTES:

INDEX SHEET 4 OF 4	
PROJECT NO. R-000265-0XXX-X	
TITLE CITY OF HOUSTON DESIGN GUIDELINE DRAWINGS FOR SUBMERSIBLE LIFT STATIONS	
CITY OF HOUSTON DEPARTMENT OF PUBLIC WORKS AND ENGINEERING ENGINEERING AND CONSTRUCTION	
APPROVALS	
WATER DESIGN	TRAFFIC AND SIGNAL DESIGN
STORM SEWER DESIGN	STREET, BRIDGE & R.O.W.
WASTEWATER DESIGN	CONSTRUCTION
OTHER REVIEWS	
PLANNING AND DEVELOPEMENT	
CITY ENGINEER	DATE
SCALE: AS NOTED	DESIGNED BY:
SUBMITTED:	DRAWN BY:
DATE:	SHEET NO. OF SHEETS
SURVEY BY:	DWG. NO.
FIELD BOOK NO.	INDEX-4

**APPENDIX B – LIST OF DESIGN REQUIREMENTS AND CONSIDERATIONS**

No.	Items
1	Provide control building for lift stations with pump rating sizes requiring MCC equipment to be indoors or as required by City of Houston Wastewater Operations.
2	Determine which station configuration is required.
3	Perform hydraulic calculations and develop system curves to determine sizes and quantities
	A. Pumps and motors (identify acceptable models from at least three manufacturers)
	B. Discharge piping and valve sizing
	C. Header and force main sizing
4	Determine necessity of and/ or sizes for:
	A. Surge relief valve(s) - If surge relief valve is required provide analysis in the final engineering design report for justification.
	B. Air release valve - An air release valve is required on all lift stations
	C. Air and vacuum valves
5	Determine piping size for wet well ventilation
6	Determine size for valve vault ventilation fan(s) and air duct(s), if required
7	Determine depth of wet well and wet well volume as it relates to pump controls
8	For control building, include design criteria and assumptions on the Drawings sufficient to obtain building permits.
9	Complete structural design criteria for the lift station and any other related structures. Provide buoyancy calculations. The criteria should include materials, loadings and load combinations, major design assumptions, and design approach. These criteria should be included as an appendix to the Final Engineering Design Report.
10	Obtain 2-year electrical service records from Utility Service Provider. Calculate the required storage capacity as defined by 30 TAC.217 and determine measures required to meet power reliability standards.



No.	Items
11	Complete and/or augment conduit and device rating schedules as necessary for specific project requirements. Determine service size from the latest Design Guideline Drawings. Obtain available fault current from Energy Service Provider and calculate fault ratings. Determine need for and size of power factor correction capacitors for 20 HP and greater.
12	Coordinate with the City's project manager to initiate electrical service/application.
13	Provide all details for site pavement cross-section, joints, connection to existing pavement, curbs, sidewalks, etc. Control and/or expansion joints shall be shown located to reduce the potential for cracking.
14	Remove all notes to Design Engineer (shown in Italics) from the Contract Drawings. Provide all information shown as TBD or as otherwise instructed in notes to Design Engineer. Revise sheet numbers, title block information, etc. as appropriate for specific project contract drawing package.
15	Dimensions on the Guideline Drawings which are modified by "max" or "min", but which need to be selected, as a definite dimension by the design engineer should have the appropriate dimension listed without the modifier.
16	Complete additional designer responsibilities as described in this manual.
17	Provide Odor Control facilities where required.
18	Comply with the Landscaping requirements of City of Houston Ordinance No. 91-1701.
19	Edit and supplement the City of Houston Standard Technical Specifications as needed to apply to the specific project.
20	Sign and seal final Contract Documents including Guideline Drawings modified or otherwise included in the Contract Drawings.
21	Provide hydraulic analysis, if required, as per Hydraulic Institute standards..
22	Provide calculations confirming the minimum pump run times to the wet well storage volume.
23	Provide wet well isolation and emergency bypass provisions.
24	Confirm the hatch cover opening will accommodate installation and removal of the selected pumps.



**APPENDIX C – BASIS OF DESIGN REPORT REQUIREMENTS FOR ETJ**

The table below summarizes the design requirements necessary for City of Houston review of ETJ lift station and force main projects. Design Engineer is to provide a Basis of Design Report with the submittal of construction drawings to the City of Houston Permitting Center.

No.	Description
1	Purpose and Scope of Project
2	Project Location
3	Map of the Service Area (Include Current and Future Areas Served by the Lift Station)
4	Site Layout
5	Lift Station Configuration Selection (Based on LS Design Guideline Manual)
6	Wet Well Design Calculations
	A. Wet Well Pump Intake Design (per Hydraulic Institute)
	B. Wet Well Sizing
	C. Wet Well Ventilation Sizing
	D. Pump Operating Levels Graphic
7	Hydraulic Design Calculations
	A. System Curves
	B. Pump Capacity Curves
	C. Discharge Piping and Valve Sizing
	D. Force Main Sizing
8	Force Main Alignment (Including Valve Sizes and Locations)
9	Air Release Valve Sizing and Location

No.	Description
10	Surge Analysis and Recommendations
11	Odor Control
12	Geotechnical Investigation Report
13	Floodplain/Floodway Analysis (with Exhibit)
14	Electrical and Instrumentation Design
15	Final Engineering Report per TCEQ Chapter 217

**APPENDIX D – SAMPLE CALCULATIONS**

DISCLAIMER: The sample calculations provided below are for reference only and may not represent all calculations needed for the design of the lift stations and force mains. It is the responsibility of the Design Engineer to perform calculations specific to each lift station and force main design. The Design Engineer shall verify the accuracy of all formulas included in the sample calculations.

## 1: FORCE MAIN SIZING

1.01 Force main size and pump station configuration should be based on sound engineering judgment and criteria provided below. Confirm all size and configuration selections with the City of Houston project manager and Wastewater Operations.

- A. In order to accommodate wet and dry weather flow variations of approximately a maximum 4:1 ratio, the number of pumps selected must be analyzed. In general, an increased number of pumps should be used as the variance between wet and dry weather flows increases.
- B. The total number of pumps should be based on the largest pump as a standby. Therefore, a 4-pump station configuration with 4-1000 gpm pumps will have a design firm station capacity of approximately 3000 gpm.
- C. An example for selection of force main size and a 3 pump or 4 pump station configuration with a maximum design flow of 4.2 mgd is as follows:

Trial No. 1 - Use 16 - inch force main

4 pump station = 3 pumps @ 1.4 mgd - min. vel. one pump = 1.55 fps

3 pump station = 2 pumps @ 2.1 mgd - min. vel. one pump = 2.3 fps

Total flow 4.2 mgd max. vel. = **4.65 fps**

Trial No. 2 - Use 14 - inch force main

4 pumps station = 3 pumps @ 1.4 mgd - min. vel. one pump = 2.02fps

3 pumps station = 2 pumps @ 2.1 mgd - min. vel. one pump = 3.03 fps

Total flow 4.2 mgd max. vel. = **6.08 fps**

- D. The selection of the pump station configuration and force main size would be for a 3-pump station with a 14-inch force main. The velocity in the 16-inch force main with 3 pump or a 4 pump station would be too low, and the velocity in the 14-inch force main for either a 3 pump or a 4 pump station @ 6.08 fps would be within recommended criteria for the total flow of 4.2 mgd.

## 2: SURGE ANALYSIS

2.01 The relationship of these various factors is expressed in the following wave speed equation:

$$a = \sqrt{\frac{K / (\frac{w}{g})}{\left(1 + C \left(\frac{D}{e}\right) \left(\frac{K}{E}\right)\right)}}$$

- A. Where:
- a = Pressure wave speed, expressed in feet per second (ft/sec)
  - D/e = A dimensionless ratio of the pipeline diameter to its wall thickness
  - E = Young's Modulus of Elasticity for the pipeline material, expressed in pounds per square foot (lb/sf) and which for steel pipe is 4,390,000,000 lb/sf; for cast iron pipe is 1,730,000,000 lb/sf; and for ductile iron pipe is 3,456,000,000 lb/sf.
  - K = Bulk Modulus of water, expressed in lb/sf and which is 43,200,000 lb/sf at 20° C.
  - w/g = Mass density of water, expressed in slugs per cubic foot which is  $62.4/32.2 = 1.938$  slugs/cf.
  - C = Coefficient of pipe support condition, which is dependent on Poisson's ratio ( $\mu$ ), which for most pipe materials the accepted  $\mu = 0.3$ .

1. The usual range of  $C_1$  is 0.85 to 1.25 and is determined as follows:
  - a.  $C_1$  for a pipe anchored at one end only, while the free end equals:
    - (1)  $1.25 - \mu = 0.95$
  - b.  $C_1$  for a pipe anchored at both ends equals:
    - (1)  $1 - (\mu)^2 = 0.91$
  - c.  $C_1$  for a pipe anchored at both ends with an expansion joint between anchors equals:
    - (1)  $1 - \frac{\mu}{2} = 0.85$
2. In addition, the pressure wave speed in water is usually in the range of 3000 to 4000 ft/sec, and using a value of 3500 ft/sec is generally sufficient for approximations.

3. Approximate Wave Speeds Examples Pipes: The following tables show approximate wave speeds in various types of pipe based on the Modulus of Elasticity (E) as shown and Poisson's ratio (Mu) at the value of 0.3.

**Table C-1. Wave Speed: Steel and Cast Iron Pipes**

D/e ratio	Wave Speed in ft/sec.	
	Steel Pipe (E=30x10 <sup>6</sup> psi)	Cast Iron Pipe (E=12x10 <sup>6</sup> psi)
25	4250	3750
50	3900	3250
75	3600	2900
100	3400	2600
150	3000	2250
200	2750	2000

**Table C-2. Wave Speed: Hobas Pipes**

D/e ratio	Wave Speed in ft/sec.		
	Class 50 psi (E=0.5x10 <sup>6</sup> psi)	Class 100 psi (E=1.2x10 <sup>6</sup> psi)	Class 250 psi (E=2.8x10 <sup>6</sup> psi)
12	1720	2450	3200
16	1510	2200	2950
20	1370	2000	2750
25	1230	1830	2550
50	890	1350	1950
75	730	1110	1640
100	630	970	1440

**Table C-3. Wave Speeds: Other Plastic Pipes**

D/e ratio	Wave Speed in ft/sec.	
	H.D.P.E. Pipe (E=0.113x10 <sup>6</sup> psi)	Other Plastic Pipe (E=1.20x10 <sup>6</sup> psi)
12	860	1130
16	750	990
20	670	890
25	603	800
50	428	570
75	350	460
100	300	400

- B. Surge Pressure - Sudden Flow Stoppage: The magnitude of surge pressure per unit change in the velocity of flow is expressed by the following equation, for the sudden or instantaneous stoppage of flow:

$$h_w = av \div g$$

Where:  $h_w$  = pressure rise expressed in feet  
 $a$  = pressure wave speed expressed in ft/sec  
 $v$  = flow velocity of the pumped fluid in ft/sec  
 $g = 32.2 \text{ ft/sec}^2$

Thus, if a liquid is flowing at a velocity of 10 ft/sec through a pipeline and is brought to a sudden stop, the increase in pressure, or surge pressure, using a pressure wave speed of 3500 ft/sec is determined as follows:

$$\begin{aligned} h_w &= av \div g = 3500 \text{ ft/sec} \times 10 \text{ ft/sec} \div 32.2 \text{ ft/sec}^2 \\ &= 35,000 \text{ ft}^2/\text{sec}^2 \div 32.2 \text{ ft/sec}^2 = 1087 \text{ ft} \end{aligned}$$

$$1087 \text{ ft} \div 2.31 \text{ ft/psi} = 470.56 \text{ psi}$$

- C. Surge Pressure - Change in Flow: The magnitude of surge pressure per unit change in the velocity of flow is expressed by the following equation, for the sudden or instantaneous stoppage of flow:

$$h_w = a/g (v_1 - v_2)$$

Where:  $v_1$  = original steady flow velocity expressed in ft/sec  
 $v_2$  = final steady flow velocity expressed in ft/sec

Thus, if a liquid is flowing at a velocity of 8 ft/sec while being pumped by two pumps, then one pump is stopped resulting in a flow velocity of 4 ft/sec, the increase in pressure or surge pressure, using a pressure wave speed of 3500 ft/sec is determined as follows:

$$h_w = a/g (v_1 - v_2) = \frac{3500 \text{ ft/sec}}{32.2 \text{ ft/sec}^2} * (8 \text{ ft/sec} - 4 \text{ ft/sec})$$

$$= 108.7 \text{ 1/sec} (4 \text{ ft/sec}) = 434.8 \text{ ft}$$

$$434.8 \text{ ft} \div 2.31 \text{ ft/psi} = 188 \text{ psi} \pm$$

1. It should be noted that as a "Rule of Thumb" the above equations will yield a surge pressure of approximately 100 ft of water (43.3 psi) per each 1 fps change in velocity.



D. Comparison: Surge Analysis by Computer Program

1. It should be noted that the above equation represents the maximum surge pressure possible for a given situation. The equation works well for simple one-pipe situations where near instantaneous flow velocity changes occur. In more complex situations, such as pumping stations or pipe networks, the use of this equation may tend to predict excessive pressures. These predictions then often lead to over design of pumping stations, pipelines, etc., which unnecessarily drives up project costs.

A more detailed analysis using a computer model will often provide a lesser, but more accurate, design pressure and also provide insight into other potential problems such as minimum and negative pressures predicted as well as the potential cavitation locations within a pipeline. The more accurate design pressures may allow the designer to specify less costly materials while still maintaining an appropriate safety factor. In complex situations, the cost of a thorough computer analysis is usually justified by total project savings. An example comparing the two methods is given below:

Using the data for Example No. 1 (Section 2.15), the surge pressures predicted by the above equation are 294 psi.

By constructing a simple computer model, the predicted pressures drop to 230 psi.

By constructing a somewhat more complex computer model, the predicted pressures drop further to 137 psi.

E. Surge Pressure Considerations

1. Pipeline Length: For pipelines of infinite length, surge pressures resulting from variations in the velocity of flow through the pipeline are not affected in magnitude by the rate at which the velocity of flow is changed. However, this effect is not true in pipelines of finite length. This difference is significant in surge pressure phenomena in actual pipelines.
2. Wave Reflection: In actual pipeline situations, surge pressure problems can become somewhat more complex because the end of the pipeline institutes the mechanism of wave reflection. That is, when the pressure wave reaches the end of the force main, it reverses direction and a wave of increased pressure travels back to the pumps or valve, where reversal of the pressure wave takes place again and a second pressure wave of reduced magnitude travels the length of the pipeline. This is repeated until steady state is reached.
3. Pipeline Friction: Pipeline friction helps to decelerate the pressure wave velocity, thus each time the pressure wave travels along the length of the pipeline in either direction, its velocity in the pipeline decreases. The change in velocity of the

pressure wave is expressed by the following equation:  $\Delta v = Gh/a$ , where,  $h$  is the difference in head (pressure) at the two ends of the force main plus the friction head, (pressure) at the average velocity of the pressure wave, during the passage of the wave. Sudden change in Flow Conditions: A change in flow conditions within a force main is considered to be "sudden" if the change is completed within the time required for the surge pressure wave to travel the length of the force main, be reflected, and return to the point of origin. This time period for the surge pressure wave to make a round trip is referred to as the "critical period" of the force main and is expressed by the equation:  $t = 2L/a$ , where  $L$  = the distance between the point of flow change, i.e. pumps or valve, and the point of wave reflection. The maximum surge pressure occurs at the point of velocity change, regardless of the rate of change in velocity.

4. Gradual Change in Flow Conditions: A change in flow conditions within a force main is considered to be "gradual" if the change is completed in a period, which is greater than the "critical period". This scenario may be considered as a series of flow velocity changes, each produced in a time equal to or less than  $2L/a$ . For "n" increments of change in velocity within the initial period of  $2L/a$ :
  - a. The greatest incremental pressure change will result from the largest incremental change in velocity.
  - b. The total pressure change during the first interval of  $2L/a$  will be the sum of the "n" incremental changes in pressure that occurred during the initial interval.
  - c. The maximum surge pressure change may, however, occur after the first  $2L/a$  interval and should be determined from an accurate analysis of the direct and reflected impulses as performed by a graphical or computer model analysis.
- F. Potential Severity of Surge Pressure: In assessing the potential severity of a possible surge pressure situation, it is necessary to determine whether the change in flow conditions are to be considered as "sudden" or "gradual". As an example, if the length of force main being considered is 1500 feet, the wave velocity is assumed to be 3500 ft/sec, the "critical period" is determined to be  $2L/a = 2 \times 1500 \text{ feet} \div 3500 \text{ ft/sec} = 0.9 \text{ seconds}$ . Since it is practically impossible to intentionally produce a significant change in velocity within 1 second or less, in pipeline sizes typically encountered, the "sudden" change case most likely will not occur, and therefore maximum surge pressures are not likely to occur. This is very characteristic of "Short" force mains, and with the exception of possible slamming of check valves, these force mains are seldom of concern, and would not require any surge relief valves or other devices.
- G. On the other hand, as an example, if the length of force main being considered is say 20,000 feet, and the wave velocity is still assumed to be 3500 ft/sec, then the "critical period" is determined to be  $2L/a = 2 \times 20,000 \text{ ft} \div 3500 \text{ ft/sec} = 11.4 \text{ seconds}$ . Under this

scenario, a substantial change in the flow velocity can be achieved within this time and is likely to be of serious concern.

- H. Probable Effects of Surge Pressure: The following brief discussion is presented to assist in ascertaining the probable effects of surge pressure by classifying the physical characteristics of the force main. Identification of the initial cause of the change in flow from the steady state must be made. The three most frequently encountered probable causes are:
- a. Opening/closing of a valve.
  - b. Starting/stopping of a pump.
  - c. Failure of the force main.
1. Typically, the manual or automatic operation of valves cannot cause a "sudden" change in the flow conditions and cause a surge pressure of concern. Pumping systems, however, are more often of a more serious concern and typically have two types of problems associated with them:
    - a. The starting/stopping of the pumps under normal operating conditions.
    - b. The pump operation under power failure conditions.
  2. Under normal operating conditions the change in flow conditions are typically controlled by valves in the pump discharge line, and may be considered as a control valve condition, which would not cause a "sudden" change in the flow condition or cause a surge pressure of concern.
  3. In a power failure condition the pumps may initiate and cause a surge pressure. If the probable effect of surge pressure is serious, according to the criteria presented above, a detailed analysis by experts is recommended.
  4. Additionally, if a pump discharge valve closes "suddenly", before the forward movement of the water column stops, cavitation of the water column may occur. Cavitation may also occur at high points in the force main during the initial phases of pressure loss in the system. Vapor cavities formed under these conditions are typically closed with violent impact upon reversal of the flow and can result in extremely high surge pressures. The analysis of surge pressures associated with cavitation requires a detailed computer analysis.
  5. Likewise, a failure of the force main can cause complex surge pressures the analysis of which would best be accomplished by performing a detailed computer analysis by an expert in the field.
- I. Classification of Pumping Systems: Table C-4 is a simple classification of pumping systems into two categories "A" and "B". Surge problems occurring under category "A"

situations are typically of minor concern and usually occur with great frequency in actual practice. The severity of the surge problems associated with the category "A" situations may be determined from the checklist presented as Table C-5.

**Table C-4. Classification of Force Mains in Pumping Systems**

	A	B
1. Type of System		
A. Single pipeline of uniform size	X	
B. Single pipeline of more than one size		X
C. Two or more parallel lines		X
D. Single or parallel system connected to a distribution grid		X
2. Profile of System		
A. Relatively flat or gradual ascending slope	X	
B. Steep slope (length less than 20 times the pump head)		X
C. Intermediate high Points		X
D. Intermediate pumps or tanks		X
3. Pump Suction conditions		
A. Suction direct from suction well	X	
B. Suction line in which the critical period ( $2L/a$ ) is 1 second or less	X	
C. Suction line in which the critical period ( $2L/a$ ) is greater than 1 second		X

Notes: <sup>(1)</sup> If the pumping system to be analyzed contains any items listed under category "B", it is recommended that the system be referred to experts for analysis.

<sup>(2)</sup> If the pumping system to be analyzed contains only items listed under category "A", proceed to Table 7.

**Table C-5. Check List for Force Mains of Category "A" Item Only**

	Y	N
1. Is "Critical Period" greater than 1.5 seconds?		
2. Is the maximum flow velocity in the force main greater than 4.0 ft/sec?		
3. Will any check valve in the force main close in less than the "critical period" ( $2L/a$ )?		
4. Will the pump or motor be damaged if allowed to run backwards, up to full speed?		
5. Is the factor of safety for the force main less than 3.5 under normal operating conditions?		
6. Are there any automatic quick closing valves in the force main set to open/close in less than 5 seconds?		
7. Are there any automatic valves within the pumping system that become inoperative due to loss of pumping system pressure?		
8. Will the pump(s) be tripped off prior to full closure of the discharge valve?		
9. Will the pump(s) be started with the discharge valve open?		

Notes: <sup>(1)</sup> If the answer to any one of the above questions 1 thru 6 is yes, there is reason for concern regarding surge pressures.

<sup>(2)</sup> If two or more of the above questions 1 thru 9 are answered yes, the situation is likely to be serious and the degree of severity will be in proportion to the number of yes answers.

2.02 Examples of Surge Pressure in a Force Main

A. The following are examples to illustrate the use of Tables C-4 and C-5 as well as the various equations presented previously, which are intended to assist in determining the probable effects of surge pressures.

B. EXAMPLE NO. 1

1. Design Data:

- a. Pumps: Three (3) identical units (1 standby),
  - (1) Rated Flow (each) = 5000 gpm (7.2 mgd).
  - (2) Station Design Capacity = 10,000 gpm (14.4 mgd).
  - (3) Assumed Pump Rundown Time Under Full Head = 1.5 Seconds.
  - (4) Rated Discharge Head = 78 Feet.
- b. Force Main: 26-inch Diameter Steel Pipe, Length = 8000 Feet.
- c. Valves: 24-inch C.I. Plug Valves (suction side).
  - (1) 18-inch C.I. Plug Valves (discharge side).
  - (2) 18-inch Swing Check Valves (discharge side).
- d. Pump Suction: Suction directly from wet well through 24-inch diameter suction pipe  $(2L/a) = 2 \times 15/3500 = < 1$  second

2. Data for Surge Pressure Analysis:

- a. Steady State Conditions:
  - (1) Flow = 14.4 mgd = 22.3 cfs
  - (2) Velocity = 6.24 ft/sec
  - (3) Total Head = 78 feet
  - (4) Static Head = 5 feet
- b. Critical Period:
  - (1) Wave Velocity,  $a = 3500$  ft/sec (assumed)

$$(2) \quad 2L/a = 2 \times 8000/3500 = 4.5 \text{ sec}$$

c. Force Main Profile:

(1) No Intermediate High Points

$$(2) \quad \text{Relative Slope} = L/\Delta H = 8000/80 = 100 > 20$$

d. Cause of initial surge pressure = power failure.

e. Sudden or gradual velocity change = sudden, since the assumed pump run down time of 1.5 seconds is less than the critical period of 4.5 seconds.

f. Maximum Surge Pressure Anticipated:

$$\begin{aligned} h_w &= av \div g = 3500 \text{ ft/sec} \times 6.24 \text{ ft/sec} \div 32.2 \text{ ft/sec}^2 \\ &= 21,840 \text{ ft}^2/\text{sec}^2 \div 32.2 \text{ ft/sec}^2 \\ &= 678.3 \text{ feet (294 psi)} \end{aligned}$$

3. Classification of Force Main:

a. Using Table C-4, all applicable items fall under the "A" category, therefore, proceed to Table C-5.

4. Force Main Check List Items:

a. Items receiving "yes" answers:

(1) No. 1. Critical period greater than 1.5 seconds.

(2) No. 2. Flow velocity greater than 4.0 ft/seconds.

b. Items receiving "questionable" answers:

(1) No. 3. Closure of check valve less than the critical period (4.5 seconds)

(2) No. 4. Will pump and/or motor be damaged by reverse rotation.

5. This example indicates that there is a potentially serious surge pressure condition that could occur due to the possible sudden closure of the check valve(s). Additionally, it indicates that there may be a concern regarding the potential damage that could be caused by reverse rotation of the pump and/or motor along with a possible need to review this condition with the manufacturer.

C. EXAMPLE NO. 2



1. Design Data: Same as for Example No. 1
2. Data For Surge Pressure Analysis:
  - a. Steady State Conditions:
    - (1) Flow  $Q_1 = 14.4 \text{ mgd} = 22.3 \text{ cfs}$   
 $Q_2 = 7.2 \text{ mgd} = 11.1 \text{ cfs}$
    - (2) Velocity  $v_1 = 6.24 \text{ ft/sec}$   
 $v_2 = 3.12 \text{ ft/sec}$
    - (3) Total Head = 78 feet
    - (4) Static Head = 5 feet
  - b. Critical Period: Same as for Example No. 1
  - c. Force Main Profile: Same as for Example No. 1
  - d. Cause of initial surge pressure = Loss of power to one of the two pumps running.
  - e. Sudden or gradual velocity change = sudden, since the assumed pump rundown time of 1.5 seconds is less than the critical period of 4.5 seconds.
  - f. Maximum Surge Pressure Anticipated:
$$h_w = a/g (v_1 - v_2) = \frac{3500 \text{ ft/sec}}{32.2 \text{ ft/sec}^2} (6.24 \text{ ft/sec} - 3.12 \text{ ft/sec})$$
$$= 108.7 \text{ 1/sec} (3.12 \text{ ft/sec})$$
$$= 339 \text{ feet (147 psi)}$$
3. Classification of Force Main:
  - a. Using Table C-4, all applicable items fall under the "A" category, therefore, proceed to Table C-5.
4. Force Main Check List Items:
  - a. Items receiving "yes" answers:
    - (1) No. 1. Critical period greater than 1.5 seconds.

- (2) No. 2. Flow velocity greater than 4.0 ft/sec initially.
- b. Items receiving "questionable" answers:
  - (1) No. 3. Closure of check valve in less than the critical period of 4.5 seconds.
  - (2) No. 4. Will pump or motor be damaged by reverse rotation.
- 5. This example indicates that there is a potentially serious surge pressure condition that could occur due to the possible sudden closure of the check valve(s). Additionally it indicates that the severity of the surge pressure will be less than if both pumps were suddenly shut down. It also indicates that there may be a concern regarding the potential damage that could be caused by reverse rotation of the pump and/or motor along with a possible need to review this condition with the manufacturer.

D. EXAMPLE NO. 3

- 1. Design Data:
  - a. Pumps: Two (2) identical units (1 standby)
    - (1) Rated Flow (each) = 3000 gpm (4.3 mgd)
    - (2) Station Design Capacity = 3000 gpm (4.3 mgd)
    - (3) Assumed Pump Rundown Time under full head = 1.5 seconds.
    - (4) Rated Discharge Head = 55 feet
  - b. Force Main: 26-inch diameter steel pipe Length = 6500 feet
  - c. Valves: 16-inch C.I. plug valves, manually operated on suction and discharge of pumps.
  - d. Pump Suction: Suction directly from wet well through 16-inch diameter suction pipe  $(2L/a) = (2 \times 15/3500) = <1$  second.
- 2. Data For Surge Pressure Analysis:
  - a. Steady State Conditions:
    - (1) Flow = 4.3 mgd = 6.65 cfs
    - (2) Velocity = 1.87 ft/sec
    - (3) Total Head = 55 feet


- (4) Static Head = 5 feet
  - b. Critical Period:
    - (1) Wave Velocity,  $a = 3500 \text{ ft/sec}$  (assumed)
    - (2)  $2L/a = 2 \times 6500/3500 = 3.7 \text{ sec}$
  - c. Force Main Profile:
    - (1) No intermediate high points.
    - (2) Relative slope =  $L/\Delta H = 6500/55 = 118 > 20$
  - d. Cause of initial surge pressure = Power failure.
  - e. Sudden or gradual velocity change = Sudden, since the assumed pump rundown time of 1.5 seconds is less than the critical period of 3.7 seconds.
  - f. Maximum Surge Pressure Anticipated:  
$$h_w = av \div g = 3500 \text{ ft/sec} \times 1.87 \text{ ft/sec} \div 32.2 \text{ ft/sec}^2$$
$$= 6545 \text{ ft}^2/\text{sec}^2 \div 32.2 \text{ ft/sec}^2$$
$$= 203.3 \text{ feet (88 psi)}$$
3. Classification of Force Main:
- a. Using Table C-4, all applicable items fall under the "A" category, therefore proceed to Table C-5.
4. Force Main Check List Items:
- a. Items receiving "yes" answers: No. 1 Critical period greater than 1.5 seconds.
  - b. Items receiving "questionable" answers: No. 4 will pump and/or motor be damaged by reverse rotation.
- E. This example indicates that there is a potentially minor surge pressure condition that could occur due to the shutdown of the pump on a loss of power. It also indicates that there may be a concern regarding the potential damage that could be caused by reverse rotation of the pump and/or motor along with a possible need to review this condition with the manufacturer.

**3: SYSTEM HEAD AND PUMP CAPACITY CURVE EXAMPLE****3.01 Example Of Construction Of System Head And Pump Capacity Curves To Determine Actual Pump Operating Capacities**

- A. The selection of the pumps is based on the analysis of system head and pump capacity curves, which determine the pumping capacities of the pumps operating alone and with the other pumps as the total dynamic head increases due to additional flow pumped through the force main.
- B. Piping head losses should be calculated in accordance with the Hydraulic Institute Standards in connection with head losses through lift station piping and valves.
- C. The pump motors should be non-over loading over the entire range of pumping, including the ability to pump into the force main under a flooded wet well condition. The water surface elevation for the flooded condition would be the rim of the lowest adjacent manhole, or the underside of the top slab, which is lower.
- D. This example of the system head and pump capacity curves is based on the following conditions:
  - 1. Force main = single and twin 26-inch force mains
  - 2. Length = 15,500 LF
  - 3. Total flow  $\pm$  20.5 mgd
  - 4. Total gpm =  $20,500,000 \div 1440 = 14,236$  gpm
  - 5. No. of pumps = 4 assuming one pump as standby
  - 6. Minimum gpm per pump =  $14,236 \text{ divided by } 3 = 4745$  gpm
  - 7. Select 4 - 5000 gpm pumps
- E. Pump Curves
- F. The pump performance curves represent the volume of liquid that can be pumped with a specified pump and impeller under a range of head conditions. The pump performance curves for the 5000-gpm pump used in this example are shown in Figure C-1. It shows the gpm pumped in relation to the various head conditions and best efficiency point with impeller 510 and is tabulated as follows:

<u>GPM</u>	<u>Head</u>
0	124
1500	108
3000	93
4500	78
6000	63
7500	48
9000	33

- G. The above values are plotted in Figure C-2 and represent the pump capacity curve for a single pump.
- H. Plotting Multiple Pumping Capacity Curves
- I. The values for multiple pump capacities are also shown in Figure C-2. These values are arrived at by constructing the 2nd and 3rd pump capacity curves as a multiple of the Pump No. 1 curve as shown in Figure C-3:



### Figure C-1 - Pump Performance Curve




Figure C-2 – System Head & Pump Capacity Curve




Figure C-3 – Typical Construction of Multiple Pump Operating Curves

J. System Head Curve

K. The system head curve represents the TDH generated by a variety of flows through the proposed or existing force main and includes the static head. As the flows through the force main increase the TDH also increases.

L. The heads generated through the twin 26-inch force main are as follows:

<u>Flow Through Force Main in GPM</u>	<u>TDH In Feet</u>
0	21
1500	21
3000	24
4500	28
6000	33
7500	39
8300	43
10,500	54
12,000	63
12,300	65
14,250	79

M. The heads generated through a single 26-inch force main are as follows:

<u>Flow Through Force Main in GPM</u>	<u>TDH In Feet</u>
0	21
1500	24
3000	32
4500	45
6000	63
7500	65
8300	88
10,500	98
12,000	172
12,300	209
14,250	250

N. The values of the twin and single 26-inch force main are plotted on the system head and pump capacity curves as shown in Figure C-2 represents the system head curves for the single 26-inch force main and for the twin 26-inch force mains.

O. Determine System Pumping Capacities For Multiple Pumps

- P. The actual pumping capacities are determined by the intersection of the system head curves for single and twin 26-inch force mains with the pump capacity curves as shown in Figure 2.
- Q. The system pump capacities based on pumping into the single or twin 26-inch force main are shown as follows:

Pump Capacities Using Single 26-inch Force Main

No. of Pumps	Increase	Capacity	TDH
	(GPM)	(GPM)	(ft)
1	6,150	6,150	65
2	1,600	7,750	88
3	600	8,350	98

Pump Capacities Using Twin 26-inch Force Main

No. of Pumps	Increase	Capacity	TDH
	(GPM)	(GPM)	(ft)
1	8,300	8,300	43
2	4,000	12,300	65
3	1,950	14,250	79

- R. The above values illustrate the wide range of the 5000-gpm pump over the range of system head conditions. A single pump ranges from 6150 to 8300 gpm. The maximum required total pumping rate of 20.5 mgd or 14,236 gpm is achieved by three pumps pumping into the twin 26-inch force main.



#### 4: WET WELL CALCULATIONS

4.01 An example calculation to determine the minimum wet well volume is provided below. This example illustrates the wet well volume requirements for a 4 pump station using the following parameters:

1. Max flow = 2370 gpm or 3.41 mgd
2. No. of pumps = 4
3. Pump capacities = 4 @ 800 gpm
4. Cycle time = 6 minutes
5. 12-inch force main, 1600 feet long
6. Wet well surface area = 120 sf

4.02 The first step would be to develop a system head curve, which will show the actual pumping capacities, based on the variable friction heads generated in the force main as each pump is turned on. Based on the system head curve pump No. 1 would pump 1080 gpm, pump No. 1 and 2 would pump 1980 gpm, and pump No. 1, 2 and 3 would pump 2370 gpm. Pump No. 4 is a standby.

4.03 The wet well volume and corresponding pumping range in feet to accommodate the 6 minute cycle for each pump as they are turned on is:

A. For Pump 1, 
$$V-1 = \frac{6.0 \text{ min.} \times 1080 \text{ gpm}}{7.48 \text{ gpm/cf} \times 4} = 217\text{cf}, H_1 = 1.8'$$

B. For Pump 2, 
$$V-2 = \frac{6.0 \text{ min.} \times (1980-1080)}{7.48 \text{ gpm/cf} \times 4} = 180\text{cf}, H_2 = 1.5'$$

C. For Pump 3, 
$$V-3 = \frac{6.0 \text{ min.} \times (2370-1980)}{7.48 \text{ gpm/cf} \times 4} = 78\text{cf}, H_2 = 0.7'$$

D. Total Wet Well Volume = 475cf, Total H = ± 4'

4.04 The following Table C-6 shows the water levels (WL), and the heights (H) that water level rises or falls between pump stop and start, and indicates the pump status (either off or on).

**Table C-6. Pump Control Schedule Example**

<u>Rising Water Level</u>			<u>Falling Water Level</u>		
<u>WL Elev.</u>	<u><math>\Delta H</math></u>	<u>Action</u>	<u>Pump Station</u>	<u>Action</u>	<u>Pump Status</u>
4.00	-	P-3 on	P-1, P-2 & P-3 on	-	P1, P-2 & P-3 on
3.30	0.7	P-2 on	P-1 & P-2 on	P-1 off	P-2 & P-3 on
1.80	1.5	P-1 on	P-1 on	P-2 off	P-3 on
0.00	1.8	-	All Stop	P-3 off	All Stop

- 4.05 A typical section showing the start and stop control levels in a wet well is shown in Figure C-4 on the following page.
- 4.06 Interior wet well design. Determine the required size for the ports in the baffle wall. The dimensions of the ports should be stated on the structural drawings. Size ports such that the velocity through all ports at firm station capacity is greater than 4.5 fps and less than 6.5 fps.





Figure C-5. Typical Wet Well Elevation Showing Pump Control Levels

**ELECTRICAL SAMPLE CALCULATIONS**

### VOLTAGE DROP CALCULATIONS

1. Assume starting pump 3 with 2 pumps at full load and all auxiliaries on. (Pump 4 on standby).
2. Use published full load amps and starting inrush amps at 460V on 480V system.
3. Power factor = 0.95.



$$V_1 = 480 - \left( \frac{801}{2} \right) \left( \frac{60 \text{ Ft}}{1000} \right) (0.101)$$

$$V_1 = 477.6V \quad V_{D1} = \frac{(480 - 477.6)}{480} = 0.50\%$$

$$V_2 = V_1 - \frac{(585)(80 \text{ Ft})}{1000} (0.308)$$

$$V_2 = 477.6 - 14.4$$

$$V_2 = 463.2 \quad V_{D2} = \frac{(480 - 463.2)}{480} = 3.50\%$$

## POWER FACTOR CORRECTION CALCULATIONS

### PUMP DATA


Rated Output	-	77 HP (57 KW)
Rated Input	-	92A @ 460V (65 KW)
Published PF @ 100%	-	0.89
Published PF @ 50%	-	0.82

### 100% LOAD

$$\text{Input KVA} = (92)(0.46) \sqrt{3} = 73 \text{ KVA}$$

$$\text{Input PF} = \frac{65 \text{ KW}}{73 \text{ KVA}} = \underline{0.89} \quad - \text{ checks with published value}$$

Input Conditions:



$$\text{KVAR}_1 = \sqrt{73^2 - 65^2}$$


$$\text{KVAR}_1 = \underline{33.2}$$

Check:

$$\alpha_1 = \cos^{-1}(0.89) = 27.1^\circ$$

$$\begin{aligned} \text{KVAR}_1 &= [\sin(\alpha_1)](73 \text{ KVA}) \\ &= (0.456)(73) \\ &= \underline{33.3} \end{aligned}$$

To Correct PF To 0.95 LAG:



$$\text{PF} = \frac{\text{KW}}{\text{KVA}_2}$$

$$\begin{aligned} \text{KVA}_2 &= \frac{\text{KW}}{\text{PF}} = \frac{65}{0.95} \\ &= 68.4 \text{ KVA} \end{aligned}$$

$$\text{KVAR}_2 = \sqrt{68.4^2 - 65^2}$$

$$\text{KVAR}_2 = 21.3$$

Check:

$$\alpha_2 = \cos^{-1}(0.95) = 18.2^\circ$$

$$\begin{aligned} \text{KVAR}_2 &= [\sin(18.2)](68.4) \\ &= \underline{21.3} \end{aligned}$$

$$\begin{aligned}
 KVAR_c &= KVAR_1 - KVAR_2 \\
 &= 33.3 - 21.3 \\
 &= \underline{12 \text{ KVAR}}
 \end{aligned}$$

Standard Commercial Sizes --> 10 KVAR or 15 KVAR

Using 10 KVAR Correction:




$$\begin{aligned}
 KVAR_2 &= KVAR_1 - KVAR_c \\
 &= 33.3 - 10 \\
 &= 23.3 \text{ KVAR}
 \end{aligned}$$

$$\begin{aligned}
 KVA_2 &= \sqrt{65^2 + 23.3^2} \\
 &= 69 \text{ KVA}
 \end{aligned}$$

$$PF = \frac{65}{69} = 0.942$$

Using 15 KVAR Correction:



$$\begin{aligned}
 KVAR_2 &= KVAR_1 - KVAR_c \\
 &= 33.3 - 15 \\
 &= 18.3 \text{ KVAR}
 \end{aligned}$$

$$\begin{aligned}
 KVA_2 &= \sqrt{65^2 + 18.3^2} \\
 &= 67.5 \text{ KVA}
 \end{aligned}$$


$$PF = \frac{65}{67.5} = 0.96$$

### 50% LOAD

100% Input KW = 65KW -->


50% Input KW = 65 KW/2 = 32.5 KW

50% PF = 0.82 -->  $KVA_{50\%} = \frac{32.5}{0.82} = 39.6 \text{ KVA}$



$$\begin{aligned}
 KVAR_{50\%} &= \sqrt{39.6^2 - 32.5^2} \\
 &= 22.6 \text{ KVAR}
 \end{aligned}$$

Using 10 KVAR Correction:




$$\begin{aligned} KVAR_2 &= KVAR_{50\%} - KVAR_c \\ &= 22.6 - 10 \\ &= 12.6 \text{ KVAR} \end{aligned}$$

$$\begin{aligned} KVA_2 &= \sqrt{32.5^2 + 12.6^2} \\ &= 34.8 \text{ KVA} \end{aligned}$$

$$PF = \frac{32.5}{34.8} = 0.933$$

Using 15 KVAR Correction:



$$\begin{aligned} KVAR_2 &= KVAR_{50\%} - KVAR_c \\ &= 22.6 - 15 \\ &= 7.6 \text{ KVAR} \end{aligned}$$

$$\begin{aligned} KVA_2 &= \sqrt{32.5^2 + 7.6^2} \\ &= 33.4 \text{ KVA} \end{aligned}$$

$$PF = \frac{32.5}{33.4} = 0.97$$

USE 15 KVAR CAPACITORS

USING 15 KVAR CAPACITORS:

$$I_c = \frac{15 \text{ KVAR}}{(0.48)\sqrt{3}} = 18A$$

Per NEC 460-8:

Minimum capacitor conductor ampacities --> of  
135% of  $I_c$  or  
33% of motor circuit conductors

$$I_c \times 135\% = (18)(1.35) = 24.3$$

Motor conductor ampacity (\*1) = 130A

$$130A / 3 = 43.3A - \text{Minimum}$$

Use \*8 CU capacitor conductors



## LOAD CALCULATIONS



MOTOR CONTROL CENTER			
CIRCUIT	DESCRIPTION	HP / KVA	FLA
1	MAIN BREAKER	---	
2	PUMP NO. 1	75 HP	96
3	PUMP NO. 2	75 HP	96
4	PUMP NO. 3	75 HP	96
5	PUMP NO. 4	75 HP	96
6	AIR CONDITIONER	10 HP	14
7	LIGHTING TRANSFORMER	5 KVA	10
TOTAL			408

LIGHTING PANEL			
CIRCUIT	DESCRIPTION	WATTS	
1	CONTROL POWER	200	
2	MCC HEATER	150	
3	PLC		250
4	AIR COMPRESOR		500
5	LIGHTS	170	
6	SPARE	500	
7	BUILDING RECPTACLES		360
8	SPARE		500
9	SPARE	500	
10	SPARE	500	
11	SPACE		500
12	SPACE		500
TOTAL WATTS		4630 WATTS	
SERVICE VOLTAGE		240 VOLTS	
TOTAL AMPERES		19 AMPS	

## FAULT CALCULATIONS




STATION TYPE		4 PUMPS @		75 HP (KVA)	
SERVICE VOLTAGE	480	BASE KV	0.48		
TRANSFORMER KVA	500	USED AS BASE KVA			
XFORMER Z – POLE MTD	0.02				
XFORMER Z – PAD MTD	0.03				
<u>FEEDERS –</u>	<u>NO.</u>	<u>AWG</u>	<u>LENGTH</u>	<u>Z tot</u>	<u>Z pu</u>
MAIN	3 –	350	100	0.002063	0.0045
PUMPS	1 –	1/0	50	0.0067	0.0145
AIR CONDITIONING	1 –	6	20	0.00988	0.0214
LIGHTING PANEL	1 –	6	20	0.00988	0.0214
<u>LOADS</u>		<u>KVA</u>	<u>Z pu</u>		
PUMPS		75	1.6667		
AIR CONDITIONING		10	12.5000		
<u>EQUIVALENT Z pu</u>		<u>POLE MTD</u>		<u>PAD MTD</u>	
XFORMER & FEEDER		0.0245		0.0345	
ALL PUMPS		2.3792			
N-1 PUMPS		1.7844			
AIR CONDITIONING		12.5214			
<u>FAULT CURRENTS</u>		<u>POLE MTD</u>	<u>PAD MTD</u>		
		<u>Z tot</u>	<u>I sc</u>	<u>Z tot</u>	<u>I sc</u>
MAIN BUS		0.0242	24870	0.0339	17744
AT MOTOR		0.0386	15564	0.0483	12458
AT LIGHTING PANEL		0.0456	13182	0.0553	10869

## SHORT CIRCUIT CALCULATIONS



**APPENDIX E – SAMPLE DRAWING MARKUP**

**FIGURE A-5**  
**INSTRUCTIONS FOR REVISING**  
**GENERAL DRAWING INFORMATION**  
**- EXAMPLE -**



MOVE TO TOP  
DESIGN ENGINEER TO READ NOTES FOR  
PERTINENT INFORMATION THEN DELETE  
OF SHEET

NOTES TO DESIGN ENGINEER

- [illegible]

**NOTES:**

1. SEE DETAIL AND STRUCTURAL DRAWINGS FOR DIMENSIONS AND INFORMATION NOT SHOWN.
2. CONTRACTOR TO CONFIRM SIZE AND LOCATION OF THE WELLS MATCHES PER SELECTED HATCH AND PUMP MANUFACTURER'S REQUIREMENTS.

PROVIDE ADDITIONAL  
NOTES AS REQUIRED

REPLACE WITH APPROPRIATE DESCRIPTION  
OF INFORMATION CONTAINED ON SHEET

REPLACE WITH SPECIFIC PROJECT NUMBER

REPLACE WITH SPECIFIC PROJECT TITLE

**PROVIDE SHEET NOS. ACCORDING TO PLACEMENT  
IN SPECIFIC PROJECT DRAWING PACKAGE**

**DELETE GUIDELINE DRAWING NO.-**

VERIFY DRAWING SCALE-

ENTER CURRENT DATE-

						CITY ENGINEER	DATE
						SPEC.	1/2" x 1"-or RESIGNED BY:
						SUBMITTED	DRAWN BY:
						DATE	DECEMBER, 1989 (1) NO. OF SHEET
						AUTH'Y BY:	DATE NO.
						FOLD BOOK No.	BZCQ1
REV. NO.	DESCRIPTION				APPROV.	DATE	